

Development Consent Conditions



DA No:	DA/252/2018
Property:	89 Robey Street, MAROUBRA NSW 2035
Proposal:	Torrens title subdivision of existing lot into 2 lots with one lot containing existing dwelling, land dedication on Ferguson Street frontage and construction of hardstand car park space to front of existing dwelling (variation to lot size control).
Recommendation:	Approval

Development Consent Conditions

GENERAL CONDITIONS

The development must be carried out in accordance with the following conditions of consent.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979, Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of environmental amenity.

Approved Plans & Supporting Documentation

1. The development must be implemented substantially in accordance with the plans and supporting documentation listed below and endorsed with Council's approved stamp, except where amended by Council in red and/or by other conditions of this consent:

Plan	Drawn by	Dated
DWG. No. DA 02_01 Issue A	Urban Future	24-April-18
DWG. No. DA 03_01 Issue A	Urban Future	24-April-18

REQUIREMENTS BEFORE A CONSTRUCTION CERTIFICATE CAN BE ISSUED

The following conditions of consent must be complied with before a 'Construction Certificate' is issued by either Randwick City Council or an Accredited Certifier. All necessary information to demonstrate compliance with the following conditions of consent must be included in the documentation for the construction certificate.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979, Environmental Planning & Assessment*

Regulation 2000, Council's development consent conditions and to achieve reasonable levels of environmental amenity.

Consent Requirements

2. The requirements and amendments detailed in the 'General Conditions' must be complied with and be included in the construction certificate plans and associated documentation.

Compliance Fee

3. A development compliance and enforcement fee of \$75 shall be paid to Council in accordance with Council's adopted Fees & Charges Pricing Policy, prior to the issue of a Construction Certificate for development.

Design Alignment levels

4. The design alignment level (the finished level of concrete, paving or the like) at the property boundary for driveways, access ramps and pathways or the like, shall be:

- **Match the back of the existing Council footpath levels along the full site frontage.**

The design alignment levels at the property boundary as issued by Council and their relationship to the Council footpath in Robey Street must be indicated on the building plans for the construction certificate (a construction note on the plans is considered satisfactory). The design alignment level at the street boundary, as issued by the Council, must be strictly adhered to.

5. The above alignment levels and the site inspection by Council's Development Engineer have been issued at a prescribed fee of \$171.00 (inclusive of GST). This amount is to be paid prior to a construction certificate being issued for the development.

Car space Design

6. The gradient of the carapace must be designed and constructed to not exceed 1 in 20 (5%) and the levels of the carapace must match the alignment levels at the property boundary (as specified by Council). Details of compliance are to be included in the construction certificate documentation.

REQUIREMENTS TO BE INCLUDED IN THE CONSTRUCTION CERTIFICATE

The requirements contained in the following conditions of consent must be complied with and details of compliance must be included in the construction certificate for the development.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979, Environmental Planning & Assessment Regulation 2000, Councils development consent conditions and to achieve reasonable levels of environmental amenity.*

Compliance with the Building Code of Australia & Relevant Standards

7. In accordance with section 4.17 (11) of the *Environmental Planning & Assessment Act 1979* and clause 98 of the *Environmental Planning & Assessment Regulation 2000*, it is a *prescribed condition* that all building work must be carried out in accordance with the provisions of the Building Code of Australia (BCA).

REQUIREMENTS PRIOR TO THE COMMENCEMENT OF ANY WORKS

The following conditions of consent must be complied with prior to the commencement of any works on the site. The necessary documentation and information must be provided to the Council or the '*Principal Certifying Authority*', as applicable.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of public health, safety and environmental amenity.

Certification and Building Inspection Requirements

8. Prior to the commencement of any building works, the following requirements must be complied with:

a) a Construction Certificate must be obtained from the Council or an accredited certifier, in accordance with the provisions of the *Environmental Planning & Assessment Act 1979*.

A copy of the construction certificate, the approved development consent plans and consent conditions must be kept on the site at all times and be made available to the Council officers and all building contractors for assessment.

b) a *Principal Certifying Authority* (PCA) must be appointed to carry out the necessary building inspections and to issue an *occupation certificate*; and

c) a *principal contractor* must be appointed for the building work and the requirements of the *Home Building Act 1989* must be satisfied accordingly; and

d) the *principal contractor* must be advised of the required *critical stage inspections* and other inspections to be carried out, as specified by the *Principal Certifying Authority*; and

e) at least two days notice must be given to the Council, in writing, prior to commencing any works.

Construction Site Management Plan

9. A *Construction Site Management Plan* must be developed and implemented prior to the commencement of any works. The construction site management plan must include the following measures, as applicable to the type of development:

- location and construction of protective site fencing / hoardings;
- location of site storage areas/sheds/equipment;
- location of building materials for construction;
- provisions for public safety;
- dust control measures;
- details of proposed sediment and erosion control measures;
- site access location and construction
- details of methods of disposal of demolition materials;
- protective measures for tree preservation;
- location and size of waste containers/bulk bins;
- provisions for temporary stormwater drainage;
- construction noise and vibration management;
- construction traffic management details;

- provisions for temporary sanitary facilities.

The site management measures must be implemented prior to the commencement of any site works and be maintained throughout the works, to the satisfaction of Council.

A copy of the Construction Site Management Plan must be provided to the Principal Certifying Authority and Council prior to commencing site works. A copy must also be maintained on site and be made available to Council officers upon

Public Utilities

10. A *Public Utility Impact Assessment* must be carried out on all public utility services on the site, roadway, nature strip, footpath, public reserve or any public areas associated with and/or adjacent to the development/building works and include relevant information from public utility authorities and exploratory trenching or pot-holing, if necessary, to determine the position and level of service.
11. The applicant must meet the full cost for telecommunication companies, gas providers, Ausgrid, and Sydney Water to adjust/repair/relocate their services as required. The applicant must make the necessary arrangements with the service authority.

REQUIREMENTS DURING CONSTRUCTION & SITE WORK

The following conditions of consent must be complied with during the demolition, excavation and construction of the development.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of public health, safety and environmental amenity during construction.

Inspections during Construction

12. Building works are required to be inspected by the *Principal Certifying Authority*, in accordance with section 6.5 of the *Environmental Planning & Assessment Act 1979* and clause 162A of the *Environmental Planning & Assessment Regulation 2000*, to monitor compliance with the relevant standards of construction, Council's development consent and the construction certificate.

Sediment & Erosion Control

13. Sediment and erosion control measures, must be implemented throughout the site works in accordance with the manual for Managing Urban Stormwater – Soils and Construction, published by Landcom.

Details must be included in the Construction Site Management Plan and a copy must be provided to the Principal Certifying Authority and Council. A copy must also be maintained on site and be made available to Council officers upon request.

Dust Control

14. During demolition excavation and construction works, dust emissions must be minimised, so as not to result in a nuisance to nearby residents or result in a potential pollution incident.

Adequate dust control measures must be provided to the site prior to the works commencing and the measures and practices must be maintained throughout the demolition, excavation and construction process, to the satisfaction of Council.

Dust control measures and practices may include:-

- *Provision of geotextile fabric to all perimeter site fencing (attached on the prevailing wind side of the site fencing).*
- *Covering of stockpiles of sand, soil and excavated material with adequately secured tarpaulins or plastic sheeting.*
- *Installation of a water sprinkling system or provision hoses or the like.*
- *Regular watering-down of all loose materials and stockpiles of sand, soil and excavated material.*
- *Minimisation/relocation of stockpiles of materials, to minimise potential for disturbance by prevailing winds.*
- *Landscaping and revegetation of disturbed areas.*

Temporary Site Fencing

15. Temporary site safety fencing or site hoarding must be provided to the perimeter of the site throughout demolition, excavation and construction works, to the satisfaction of Council, in accordance with the following requirements:

- a) Temporary site fences or hoardings must have a height of 1.8 metres and be a cyclone wire fence (with geotextile fabric attached to the inside of the fence to provide dust control), or heavy-duty plywood sheeting (painted white), or other material approved by Council.
- b) Hoardings and site fencing must be designed to prevent any substance from, or in connection with, the work from falling into the public place or adjoining premises and if necessary, be provided with artificial lighting.
- c) All site fencing and hoardings must be structurally adequate, safe and be constructed in a professional manner and the use of poor quality materials or steel reinforcement mesh as fencing is not permissible.
- d) An overhead ('B' Class) type hoarding is required to be provided to protect the public (unless otherwise approved by Council) if:
 - materials are to be hoisted (i.e. via a crane or hoist) over a public footway;
 - building or demolition works are to be carried out on buildings which are over 7.5m in height and located within 3.6m of the street alignment;
 - it is necessary to prevent articles or materials from falling and causing a potential danger or hazard to the public or occupants upon adjoining land;
 - as may otherwise be required by WorkCover, Council or the PCA.

Notes:

- *Temporary site fencing may not be necessary if there is an existing adequate fence in place having a minimum height of 1.5m.*
- *If it is proposed to locate any site fencing, hoardings, amenities or articles upon any part of the footpath, nature strip or public place at any time, a separate Local Approval application must be submitted to and approved by*

Council's Health, Building & Regulatory Services before placing any fencing, hoarding or other article on the road, footpath or nature strip.

Public Safety & Site Management

16. Public safety and convenience must be maintained at all times during demolition, excavation and construction works and the following requirements must be complied with to the satisfaction of Council:

- a) Building materials, sand, soil, waste materials, construction equipment or other articles must not be placed upon the footpath, roadway or nature strip at any time.
- b) The road, footpath, vehicular crossing and nature strip must be maintained in a good, safe, clean condition and free from any excavations, obstructions, trip hazards, goods, materials, soils or debris at all times. Any damage caused to the road, footway, vehicular crossing, nature strip or any public place must be repaired immediately, to the satisfaction of Council.
- c) All building and site activities (including storage or placement of materials or waste and concrete mixing/pouring/pumping activities) must not cause or be likely to cause 'pollution' of any waters, including any stormwater drainage systems, street gutters or roadways.

Note: It is an offence under the Protection of the Environment Operations Act 1997 to cause or be likely to cause 'pollution of waters', which may result in significant penalties and fines.

- d) Access gates and doorways within site fencing, hoardings and temporary site buildings or amenities must not open outwards into the road or footway.
- e) Bulk bins/waste containers must not be located upon the footpath, roadway or nature strip at any time without the prior written approval of the Council. Applications to place a waste container in a public place can be made to Council's Health, Building and Regulatory Services department.
- f) Adequate provisions must be made to ensure pedestrian safety and traffic flow during the site works, and traffic control measures are to be implemented in accordance with the relevant provisions of the Roads and Traffic Manual "Traffic Control at Work Sites" (Version 4), to the satisfaction of Council.

Site Signage

17. A sign must be erected and maintained in a prominent position on the site for the duration of the works, which contains the following details:

- name, address, contractor licence number and telephone number of the *principal contractor*, including a telephone number at which the person may be contacted outside working hours, or *owner-builder* permit details (as applicable)
- name, address and telephone number of the *Principal Certifying Authority*,
- a statement stating that "unauthorised entry to the work site is prohibited".

Restriction on Working Hours

18. Building, demolition and associated site works must be carried out in accordance with the following requirements:

Activity	Permitted working hours
All building, demolition and site work, including site deliveries (except as detailed below)	<ul style="list-style-type: none"> Monday to Friday - 7.00am to 5.00pm Saturday - 8.00am to 5.00pm Sunday & public holidays - No work permitted
Excavating or sawing of rock, use of jack-hammers, pile-drivers, vibratory rollers/compactors or the like	<ul style="list-style-type: none"> Monday to Friday - 8.00am to 1.00pm only Saturday - No work permitted Sunday & public holidays - No work permitted
Additional requirements for all development	<ul style="list-style-type: none"> Saturdays and Sundays where the preceding Friday and/or the following Monday is a public holiday - No work permitted

An application to vary the abovementioned hours may be submitted to Council's Manager Health, Building & Regulatory Services for consideration and approval to vary the specified hours may be granted in exceptional circumstances and for limited occasions (e.g. for public safety, traffic management or road safety reasons). Any applications are to be made on the standard application form and include payment of the relevant fees and supporting information. Applications must be made at least 10 days prior to the date of the proposed work and the prior written approval of Council must be obtained to vary the standard permitted working hours.

Building Encroachments

19. There must be no encroachment of any structures or building work onto Council's road reserve, footway, nature strip or public place.

Tree Management

20. Approval is granted for removal of the *Banksia serrata* (Saw Toothed Banksia) located centrally in the front setback of the subject site so as to accommodate the new vehicle crossing and internal hardstand in this same area as shown.

REQUIREMENTS PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE

The following conditions of consent must be complied with prior to the 'Principal Certifying Authority' issuing an 'Occupation Certificate'.

Note: For the purpose of this consent, any reference to 'occupation certificate' shall also be taken to mean 'interim occupation certificate' unless otherwise stated.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979, Environmental Planning & Assessment Regulation 2000*, Council's development consent and to maintain reasonable levels of public health, safety and amenity.

Occupation Certificate Requirements

21. An Occupation Certificate must be obtained from the Principal Certifying Authority prior to any occupation of the building work encompassed in this development consent (including alterations and additions to existing buildings), in accordance

with the relevant provisions of the *Environmental Planning & Assessment Act 1979*.

Council's Infrastructure, Vehicular Crossings, street verge

22. The applicant must meet the full cost for a Council approved contractor to:
 - a. Construct a concrete vehicular crossing and layback at kerb opposite the vehicular entrance to the site in Robey Street, to Council's specifications and requirements.
23. The applicant must meet the full cost for Council or a Council approved contractor to repair/replace any damaged sections of Council's footpath, kerb & gutter, nature strip etc which are due to building works being carried out at the above site. This includes the removal of cement slurry from Council's footpath and roadway.
24. All external civil work to be carried out on Council property (including the installation and repair of roads, footpaths, vehicular crossings, kerb and guttering and drainage works), must be carried out in accordance with Council's "Crossings and Entrances – Contributions Policy" and "Residents' Requests for Special Verge Crossings Policy" and the following requirements:
 - a) Details of the proposed civil works to be carried out on Council land must be submitted to Council in a Civil Works Application Form. Council will respond, typically within 4 weeks, with a letter of approval outlining conditions for working on Council land, associated fees and workmanship bonds. Council will also provide details of the approved works including specifications and construction details.
 - b) Works on Council land, must not commence until the written letter of approval has been obtained from Council and heavy construction works within the property are complete. The work must be carried out in accordance with the conditions of development consent, Council's conditions for working on Council land, design details and payment of the fees and bonds outlined in the letter of approval.
 - c) The civil works must be completed in accordance with the above, prior to the issuing of an occupation certificate for the development, or as otherwise approved by Council in writing.
25. That part of the nature-strip upon Council's footway which is damaged during the course of the works shall be re-graded and re-turfed with Kikuyu Turf rolls, including turf underlay, wholly at the applicant's cost, to Council's satisfaction, prior to the issue of any Occupation Certificate.

Street and/or Sub-Address Numbering

26. Street numbering must be provided to the front of the premises in a prominent position, in accordance with the Australia Post guidelines and AS/NZS 4819 (2003) to the satisfaction of Council.

If this application results in an additional lot, dwelling or unit, an application must be submitted to and approved by Council's Director of City Planning, together with the required fee, for the allocation of appropriate street and/or unit numbers for the development. The street and/or unit numbers must be allocated prior to the issue of an occupation certificate.

Please note: any Street or Sub-Address Numbering provided by an applicant on plans, which have been stamped as approved by Council are not to be interpreted as endorsed, approved by, or to the satisfaction of Council.

REQUIREMENTS PRIOR TO THE ISSUE OF A SUBDIVISION CERTIFICATE

The following conditions of consent must be complied with prior to the 'Principal Certifying Authority' issuing a 'Subdivision certificate'.

These conditions have been applied to satisfy the provisions of Council's environmental plans, policies and codes for subdivision works.

Sydney Water

27. A compliance certificate must be obtained from Sydney Water, under Section 73 of the Sydney Water Act 1994. Sydney Water's assessment will determine the availability of water and sewer services, which may require extension, adjustment or connection to their mains, and if required will issue a Notice of Requirements letter detailing all requirements that must be met. Applications can be made either directly to Sydney Water or through a Sydney Water accredited Water Servicing Coordinator (WSC).

Go to sydneywater.com.au/section73 or call 1300 082 746 to learn more about applying through an authorised WSC or Sydney Water.

A Section 73 Compliance Certificate must be completed before a subdivision certificate will be issued.

Subdivision Plans

28. The applicant shall create suitable rights of carriageway, easements for services, support and stormwater lines, as required. The applicant shall be advised that the minimum easement width for any stormwater line is 0.9 metres.

Road Widening Dedication

29. The applicant shall dedicate a strip of land 4.57 metres wide along the Ferguson Street frontage for road widening purposes. All costs associated with the dedication shall be borne by the applicant.
30. The applicant shall pay to Council the sum of \$2,481.48 (based on a rate of \$366.00 per lineal metre of road frontage along Ferguson Street), as a contribution towards the cost of the reconstruction of Ferguson Street and in conjunction with the road dedication and in compliance with Council's subdivision policy.

Removal of Structures Ferguson Street

31. The applicant is to have removed the rear timber boundary fencing located within the dedicated strip of land, this shall also include the portion of the northern side timber boundary fencing also located within the road dedication.
32. The applicant shall regrade and turf the section of land to be dedicated for road widening to Council's satisfaction.

Subdivision Certificate

33. A formal application for a subdivision certificate is required to be submitted to and approved by the Council and all relevant conditions of this development consent are required to be satisfied prior to the release of the subdivision plans including the construction of the off-street car space fronting Robey Street.

GENERAL ADVISORY NOTES

The following information is provided for your assistance to ensure compliance with the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000*, or other relevant legislation and requirements. This information does not form part of the conditions of development consent pursuant to Section 4.17 of the Act.

- A1 The requirements and provisions of the *Environmental Planning & Assessment Act 1979* and *Environmental Planning & Assessment Regulation 2000*, must be fully complied with at all times.

Failure to comply with these requirements is an offence, which renders the responsible person liable to a maximum penalty of \$1.1 million. Alternatively, Council may issue a penalty infringement notice (for up to \$6,000) for each offence. Council may also issue notices and orders to demolish unauthorised or non-complying building work, or to comply with the requirements of Council's development consent.

- A2 In accordance with the requirements of the *Environmental Planning & Assessment Act 1979*, building works, including associated demolition and excavation works (as applicable) must not be commenced until:

- A *Construction Certificate* has been obtained from an Accredited Certifier or Council,
- An Accredited Certifier or Council has been appointed as the *Principal Certifying Authority* for the development,
- Council and the Principal Certifying Authority have been given at least 2 days notice (in writing) prior to commencing any works.

- A3 Council can issue your *Construction Certificate* and be your *Principal Certifying Authority* for the development, to undertake inspections and ensure compliance with the development consent and relevant building regulations. For further details contact Council on 9093 6944.

- A4 This determination does not include an assessment of the proposed works under the Building Code of Australia (BCA), Disability (Access to Premises – Buildings) Standards 2010 and other relevant Standards. All new building work (including alterations and additions) must comply with the BCA and relevant Standards. You are advised to liaise with your architect, engineer and building consultant prior to lodgement of your construction certificate.

- A5 Any proposed amendments to the design and construction of the building may require a new development application or a section 4.55 amendment to the existing consent to be obtained from Council, before carrying out such works

- A6 A Local Approval application must be submitted to and be approved by Council prior to commencing any of the following activities on a footpath, road, nature strip or in any public place:-

- Install or erect any site fencing, hoardings or site structures
- Operate a crane or hoist goods or materials over a footpath or road
- Placement of a waste skip or any other container or article.

For further information please contact Council on 9093 6971.

A7 Specific details of the location of the building/s should be provided in the Construction Certificate to demonstrate that the proposed building work will not encroach onto the adjoining properties, Council's road reserve or any public place.

A8 This consent does not authorise any trespass or encroachment upon any adjoining or supported land or building whether private or public. Where any underpinning, shoring, soil anchoring (temporary or permanent) or the like is proposed to be carried out upon any adjoining or supported land, the land owner or principal contractor must obtain:

- the consent of the owners of such adjoining or supported land to trespass or encroach, or
- an access order under the *Access to Neighbouring Land Act 2000*, or
- an easement under section 88K of the *Conveyancing Act 1919*, or
- an easement under section 40 of the *Land & Environment Court Act 1979*, as appropriate.

Section 177 of the *Conveyancing Act 1919* creates a statutory duty of care in relation to support of land. Accordingly, a person has a duty of care not to do anything on or in relation to land being developed (the supporting land) that removes the support provided by the supporting land to any other adjoining land (the supported land).

A9 External paths and ground surfaces are to be constructed at appropriate levels and be graded and drained away from the building and adjoining premises, so as not to result in the entry of water into the building, or cause a nuisance or damage to any adjoining land.

Finished ground levels external to the building are to be consistent with the development consent and are not to be raised, other than for the provision of approved paving or the like on the ground.

A10 Prior to commencing any works, the owner/builder should contact *Dial Before You Dig* on 1100 or www.dialbeforeyoudig.com.au and relevant Service Authorities, for information on potential underground pipes and cables within the vicinity of the development site.

A11 The necessary development consent and a construction certificate or a complying development certificate (as applicable) must be obtained for any proposed *cooling towers* and external plant and equipment, if not included in this consent.

A12 An application must be submitted to an approved by Council prior to the installation and operation of any proposed greywater or wastewater treatment systems, in accordance with the *Local Government Act 1993*.

Greywater/Wastewater treatment systems must comply with the relevant requirements and guidelines produced by NSW Health, NSW Office of Environment and Heritage and other relevant regulatory requirements.

A13 There are to be no emissions or discharges from the premises, which will give rise to an environmental or public nuisance or result in an offence under the *Protection of the Environment Operations Act 1997* and *Regulations*.

- A14 The applicant is to advise Council in writing and/or photographs of any signs of existing damage to the Council roadway, footway, or verge prior to the commencement of any building/demolition works.
- A15 The applicant is formally advised that, as part of any future development within the newly created Lot, Council will need to impose conditions to ensure the ongoing protection and retention of the established *Lophostemon confertus* (Brush Box) that is located wholly in the rear yard of the adjoining private property at no.91, against the common boundary. This tree must be viewed as a site constraint to any future development of the newly created Lot fronting Ferguson Street.