

Development Consent Conditions (dwellings and dual occupancies)



Folder /DA No:	DA/508/2018
Property:	96 Tunstall Avenue, KINGSFORD NSW 2032
Proposal:	Demolition of all structures on site and construction of a new part 2 and part 3 storey dwelling house with double garage, rear swimming pool, associated site and landscaping works.
Recommendation:	Approval

Development Consent Conditions

GENERAL CONDITIONS

The development must be carried out in accordance with the following conditions of consent.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of environmental amenity.

Approved Plans & Supporting Documentation

- The development must be implemented substantially in accordance with the plans and supporting documentation listed below and endorsed with Council's approved stamp, except where amended by Council in red and/or by other conditions of this consent:

Plan	Drawn by	Dated
Site Plan A104 Revision 2	Aetch Design	14 March 2019
Lower Ground Floor Plan A105 Revision 2	Aetch Design	14 March 2019
Entry Floor Plan A106 Revision 2	Aetch Design	14 March 2019
First Floor Plan A107 Revision 2	Aetch Design	14 March 2019
FSR Diagrams A108 Revision 2	Aetch Design	14 March 2019
Site Diagrams Elevation A109 Revision 2	Aetch Design	14 March 2019
East Elevation A201 Revision 2	Aetch Design	14 March 2019
West Elevation A202 Revision 2	Aetch Design	14 March 2019
North Elevation A203 Revision 2	Aetch Design	14 March 2019
South Elevation A204 Revision 2	Aetch Design	14 March 2019
Street Elevations & Rear (West)A205 Revision 2	Aetch Design	14 March 2019
A301 Section A-A Revision 2	Aetch Design	14 March 2019
A302 Section B & C Revision 2	Aetch Design	14 March 2019
A303 Section D – D Revision 2	Aetch Design	14 March 2019
A501 Materials Schedule Revision 2	Aetch Design	14 March 2019

<i>BASIX Certificate No.</i>	<i>Dated</i>
947075S	15 August 2018

Amendment of Plans & Documentation

2. The approved plans and documents must be amended in accordance with the following requirements:

- a. A privacy screen having a height of 1.6 m (measured above floor level) shall be provided to the deck adjoining the laundry at entry floor level on the southern elevation.

Privacy screen/s must be constructed with either:

- Translucent or obscured glazing (The use of film applied to the clear glass pane is unacceptable);
- Fixed lattice/slats with individual openings not more than 30mm wide;
- Fixed vertical or horizontal louvres with the individual blades angled and spaced appropriately to prevent overlooking into the private open space or windows of the adjacent dwellings.

- b. The bench on the southern edge of the deck adjoining the living area at lower ground level shall be removed and replaced with deep soil landscape and a privacy screen having a height of 1.6 m (measured above floor level) shall be provided on the inside face of the external on the southern elevation.

Privacy screen/s must be constructed with either:

- Translucent or obscured glazing (The use of film applied to the clear glass pane is unacceptable);
- Fixed lattice/slats with individual openings not more than 30mm wide;
- Fixed vertical or horizontal louvres with the individual blades angled and spaced appropriately to prevent overlooking into the private open space or windows of the adjacent dwellings.

- c. The following window/s must have a minimum sill height of 1.6m above floor level, or alternatively, the window/s are to be fixed and be provided with translucent, obscured, frosted or sandblasted glazing below this specified height:

- bedroom 4 window (3.08) on the northern elevation at the first floor
- living room window (1.08) on southern elevation at lower ground floor
- bedroom 3 window (2.09) on western elevation at ground floor (entry floor plan)

- d. Detailed Landscape Plan substantially consistent with the Landscape Plan prepared by Secret Gardens dated 8 August 2018 Revision B and as amended by the Lower Ground A105 dated 14 March 2019 and Entry Floor Plan A106 dated 14 March 2019 prepared by AETCH Designs. The Detailed Landscape Plan shall show the screen planting, including tree/plant species and mature heights within the landscape planter setback along the southern boundary adjoining the turf area and the landscape planter setback along the northern boundary between the outdoor deck and BBQ area and include section plans with existing ground/pool levels of the adjoining properties.

- e. The fence on the front street alignment is to be a maximum height of 1.2 m and be designed so the upper two thirds of the fence (excluding any piers or

posts) is at least 50% open, to maintain reasonable levels of amenity to the adjoining residential development and the streetscape.

- f. Fences located on the side boundaries of the site shall not exceed a maximum height of 1.8 m measured above existing ground levels, except for the southern boundary adjoining the turf area at the rear. On sloping sites or in changes at ground levels, the maximum height of the fence may exceed the aforementioned specified height by up to 150 mm maximum adjacent to any required 'step downs' or changes in ground level. Alternatively separate development consent must be obtained for alternative side and rear boundary fencing.
- g. The sink in the living area at the top floor shall be removed.

REQUIREMENTS BEFORE A CONSTRUCTION CERTIFICATE CAN BE ISSUED

The following conditions of consent must be complied with before a 'Construction Certificate' is issued by either Randwick City Council or an Accredited Certifier. All necessary information to demonstrate compliance with the following conditions of consent must be included in the documentation for the construction certificate.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000*, Council's development consent conditions and to achieve reasonable levels of environmental amenity.

Consent Requirements

3. The requirements and amendments detailed in the 'General Conditions' must be complied with and be included in the construction certificate plans and associated documentation.

External Colours, Materials & Finishes

4. The colours, materials and surface finishes to the development must be consistent with the relevant plans, documentation and colour schedules provided with the development application.

Section 7.12 Development Contributions

5. In accordance with Council's Development Contributions Plan effective from 21 April 2015, based on the development cost of \$2,602,080 the following applicable monetary levy must be paid to Council: \$26,020.80.

The levy must be paid in **cash, bank cheque** or by **credit card** prior to a construction certificate being issued for the proposed development. The development is subject to an index to reflect quarterly variations in the Consumer Price Index (CPI) from the date of Council's determination to the date of payment. Please contact Council on telephone 9093 6999 or 1300 722 542 for the indexed contribution amount prior to payment.

To calculate the indexed levy, the following formula must be used:

$$\mathbf{IDC = ODC \times CP2/CP1}$$

Where:

IDC = the indexed development cost

ODC = the original development cost determined by the Council

CP2 = the Consumer Price Index, All Groups, Sydney, as published by the ABS in respect of the quarter ending immediately prior to the date of payment

CP1 = the Consumer Price Index, All Groups, Sydney as published by the ABS in respect of the quarter ending immediately prior to the date of imposition of the condition requiring payment of the levy.

Council's Development Contribution Plans may be inspected at the Customer Service Centre, Administrative Centre, 30 Frances Street, Randwick or at www.randwick.nsw.gov.au.

Compliance Fee

6. A development compliance and enforcement fee of \$2,602 shall be paid to Council in accordance with Council's adopted Fees & Charges Pricing Policy, prior to the issue of a Construction Certificate for development.

Long Service Levy Payments

7. The required Long Service Levy payment, under the *Building and Construction Industry Long Service Payments Act 1986*, must be forwarded to the Long Service Levy Corporation or the Council, in accordance with Section 6.8 of the *Environmental Planning & Assessment Act 1979*.

At the time of this development consent, Long Service Levy payment is applicable on building work having a value of \$25,000 or more, at the rate of 0.35% of the cost of the works.

Security Deposit

8. The following damage / civil works security deposit requirement must be complied with as security for making good any damage caused to the roadway, footway, verge or any public place; and as security for completing any public work; and for remedying any defect on such public works, in accordance with section 80A(6) of the *Environmental Planning and Assessment Act 1979*:

- \$3000.00 - Damage / Civil Works Security Deposit

The damage/civil works security deposit may be provided by way of a cash, cheque or credit card payment and is refundable upon a satisfactory inspection by Council upon the completion of the civil works which confirms that there has been no damage to Council's infrastructure.

The owner/builder is also requested to advise Council in writing and/or photographs of any signs of existing damage to the Council roadway, footway, or verge prior to the commencement of any building/demolition works.

To obtain a refund of relevant deposits, a *Security Deposit Refund Form* is to be forwarded to Council's Director of City Services upon issuing of an occupation certificate or completion of the civil works.

Design Alignment levels

9. The design alignment level (the finished level of concrete, paving or the like) at the property boundary for driveways, access ramps and pathways or the like, shall be:

- **Match the back of the existing Council footpath levels along the full site frontage.**

The design alignment levels at the property boundary as issued by Council and their relationship to the Council footpath must be indicated on the building plans for the construction certificate (a construction note on the plans for the construction certificate is considered satisfactory). The design alignment level at the street boundary, as issued by the Council, must be strictly adhered to.

Any request to vary the design alignment level/s must be forwarded to and approved in writing by Council's Development Engineers and may require a formal amendment to the development consent via a Section 4.55 application.

10. The above alignment levels and the site inspection by Council's Development Engineering Section have been issued at a prescribed fee of \$889.00 calculated at \$53.00 per metre of site frontage. This amount is to be paid prior to a construction certificate being issued for the development.

Sydney Water

11. All building, plumbing and drainage work must be carried out in accordance with the requirements of the Sydney Water Corporation.

The approved plans must be submitted to the Sydney Water Tap in™ online service, to determine whether the development will affect Sydney Water's waste water and water mains, stormwater drains and/or easements, and if any further requirements need to be met.

The Sydney Water Tap in™ online service replaces the Quick Check Agents as of 30 November 2015

The Tap in™ service provides 24/7 access to a range of services, including:

- Building plan approvals
- Connection and disconnection approvals
- Diagrams
- Trade waste approvals
- Pressure information
- Water meter installations
- Pressure boosting and pump approvals
- Change to an existing service or asset, e.g. relocating or moving an asset.

Sydney Water's Tap in™ in online service is available at:

<https://www.sydneywater.com.au/SW/plumbing-building-developing/building/sydney-water-tap-in/index.htm>

The Principal Certifying Authority must ensure that the developer/owner has submitted the approved plans to Sydney Water Tap in online service.

Stormwater Drainage

12. Detailed drainage plans with levels reduced to Australian Height Datum (AHD), shall be prepared by a suitably qualified Hydraulic Engineer and be submitted to and approved by the certifying authority. A copy of the plans shall be forwarded to Council, if Council is not the certifying authority.

The drainage plans must demonstrate compliance with the Building Code of Australia, Australian Standard AS3500.3:2003 (Plumbing and Drainage - Stormwater Drainage) and the relevant conditions of this development approval.

13. A site stormwater drainage system is to be provided in accordance with the following requirements (as applicable):
 - a) The stormwater drainage system must be designed and constructed to satisfy the relevant requirements in the Building Code of Australia,
 - b) Roof stormwater must be directed to a suitably designed and constructed rainwater tank, as required in the relevant BASIX Certificate for the dwelling,

- c) The overflow from the rainwater tank and other surface stormwater must be directed (via a sediment/silt arrestor pit) to:
 - i. A suitably sized infiltration area to the satisfaction of the Certifying Authority. As a guide, infiltration areas which do not have a formal overflow to the street should be sized based on a minimum requirement of 1 m² of infiltration area (together with 1 m³ of storage volume) for every 20 m² of roof/impervious area draining to the infiltration area.
- d) The design and construction of the infiltration areas must be appropriate having regard to the site and ground characteristics.

Infiltration areas must be a minimum of 3.0 metres from any structure (note: this setback requirement may not be necessary if a structural engineer or other suitably qualified person certifies that the infiltration area will not adversely affect the structure) and 2.1 metres from any adjacent side or rear boundary.

If there is no formal overland escape route from the infiltration area to Council's kerb and gutter/street drainage system, a suitable investigation is required to be carried out by a *professional engineer* to determine the suitability of the ground for infiltration and the design of the proposed infiltration system,

Infiltration will not be appropriate if the site is subject to rock and/or a water table within 2 metres of the base of the infiltration area, or the ground conditions comprise low permeability soils such as clay.

Should the site or ground conditions preclude the construction of an infiltration pit (i.e. due to rock etc), consideration may be given to the installation of a suitably designed pump-out system,

- e) Pump-out systems must be designed by a suitably qualified and experienced hydraulic consultant/engineer and the pump-out system designed and constructed generally in accordance with Council's Stormwater Code.

Pump-out systems must be provided with two pumps and be installed, connected in parallel (with each pump being capable of discharging at the required discharge rate) and connected to a control board so that each pump will operate alternatively. The pump wet well is required to be sized for the 1 in 100 year, 2 hour storm assuming both pumps are not working,

- f) Any pump-out water must pass through a stilling pit prior to being discharged by gravity to the kerb and gutter,
- g) Details of the design and construction of the stormwater drainage system, sediment site arrestor pit/s and infiltration area/s must be submitted to and approved by the Certifying Authority with the Construction Certificate and all works are to be carried to the satisfaction of the Principal Certifying Authority.

- 14. Sediment/silt arrestor pit/s are to be provided within the site at or near the street boundary prior to stormwater being discharged from the site or into any infiltration areas. The sediment/silt arrestor pits are to be constructed generally in accordance with the following requirements, to the satisfaction of the principal certifying authority:

- The base of the pit located a minimum 300mm under the invert level of the outlet pipe.

- The grate is to be a galvanised heavy-duty grate that has a provision for a child proof fastening system.
- A minimum of 4 x 90 mm diameter weep holes located in the walls of the pit at the floor level with a suitable geotextile material with a high filtration rating located over the weep holes.
- A galvanised heavy-duty screen located over the outlet pipe (Mascot GMS Multi-purpose filter screen or similar)
- A child proof and corrosion resistant fastening system for the access grate (spring loaded j-bolts or similar).
- The inlet pipeline located on the side of the pit so that the stormwater will discharge across the face of the screen.
- A sign adjacent to this pit stating that:
"This sediment/silt arrester pit shall be regularly inspected and cleaned."

Landscape Plan

15. The Certifying Authority/PCA must ensure that the Detailed Landscape Plans submitted as part of the approved Construction Certificate are substantially consistent with the amended landscape regime shown in Lower Ground A105 dated 14 March 2019 and Entry Floor Plan A106 dated 14 March 2019.

Street Tree Management

16. The applicant must submit a payment of **\$297.50** (plus GST), to cover the following costs:
- a. For Council to remove, stump-grind and dispose of the unauthorized planting of *Duranta erecta* (Golden Dewdrop) from the Tunstall Avenue verge, to the north of the existing vehicle crossing, centrally across the width of the site;
 - b. For Council to supply, plant and maintain 1 x 25 litre *Ulmus parvifolia* (Chinese Weeping Elm) back on the Tunstall Avenue verge, an equal distance between the northern edge of the new vehicle crossing and northern site boundary, at the completion of all works.

This fee must be paid into **Tree Amenity Income** at the Cashier on the Ground Floor of the Administrative Centre **prior to a Construction Certificate being issued for the development.**

The applicant must contact Council's Landscape Development Officer on 9093-6613 (quoting the receipt number), and giving at least four working weeks-notice (allow longer for public holidays or extended periods of rain) to arrange for removal of the existing tree prior to the commencement of site works, as well as upon completion, to arrange for planting of the replacement.

After this, any further enquiries regarding scheduling/timing or completion of works are to be directed to Council's Tree Preservation & Maintenance Coordinator on 9093-6858.

REQUIREMENTS TO BE INCLUDED IN THE CONSTRUCTION CERTIFICATE

The requirements contained in the following conditions of consent must be complied with and details of compliance must be included in the construction certificate for the development.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979, Environmental Planning & Assessment*

Regulation 2000, Councils development consent conditions and to achieve reasonable levels of environmental amenity.

Compliance with the Building Code of Australia & Relevant Standards

17. In accordance with section 4.17 (11) of the *Environmental Planning & Assessment Act 1979* and clause 98 of the *Environmental Planning & Assessment Regulation 2000*, it is a *prescribed condition* that all building work must be carried out in accordance with the provisions of the Building Code of Australia (BCA).

BASIX Requirements

18. In accordance with section 4.17 (11) of the *Environmental Planning & Assessment Act 1979* and clause 97A of the *Environmental Planning & Assessment Regulation 2000*, the requirements and commitments contained in the relevant BASIX Certificate must be complied with.

The required commitments listed and identified in the BASIX Certificate must be included on the construction certificate plans, specifications and associated documentation, to the satisfaction of the Certifying Authority.

The design of the building must not be inconsistent with the development consent and any proposed variations to the building to achieve the BASIX commitments may necessitate a new development consent or amendment to the existing consent to be obtained, prior to a construction certificate being issued.

REQUIREMENTS PRIOR TO THE COMMENCEMENT OF ANY WORKS

The following conditions of consent must be complied with prior to the commencement of any works on the site. The necessary documentation and information must be provided to the Council or the '*Principal Certifying Authority*', as applicable.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of public health, safety and environmental amenity.

Certification and Building Inspection Requirements

19. Prior to the commencement of any building works, the following requirements must be complied with:

- a) a Construction Certificate must be obtained from the Council or an accredited certifier, in accordance with the provisions of the *Environmental Planning & Assessment Act 1979*.

A copy of the construction certificate, the approved development consent plans and consent conditions must be kept on the site at all times and be made available to the Council officers and all building contractors for assessment.

- b) a *Principal Certifying Authority* (PCA) must be appointed to carry out the necessary building inspections and to issue an *occupation certificate*; and
- c) a *principal contractor* must be appointed for the building work, or in relation to residential building work, an *owner-builder* permit may be obtained in accordance with the requirements of the *Home Building Act 1989*, and the PCA and Council are to be notified accordingly; and

- d) the *principal contractor* must be advised of the required *critical stage inspections* and other inspections to be carried out, as specified by the *Principal Certifying Authority*; and
- e) at least two days notice must be given to the Council, in writing, prior to commencing any works.

Home Building Act 1989

20. In accordance with section 4.17 (11) of the Environmental Planning & Assessment Act 1979 and clause 98 of the Environmental Planning & Assessment Regulation 2000, the relevant requirements of the Home Building Act 1989 must be complied with.

Details of the Licensed Building Contractor and a copy of the relevant Certificate of Home Warranty Insurance or a copy of the Owner-Builder Permit (as applicable) must be provided to the Principal Certifying Authority and Council.

Dilapidation Reports

21. A dilapidation report must be obtained from a Professional Engineer, Building Surveyor or other suitably qualified independent person, in the following cases:

- excavations for new dwellings, additions to dwellings, swimming pools or other substantial structures which are proposed to be located within the *zone of influence* of the footings of any dwelling, associated garage or other substantial structure located upon an adjoining premises;
- new dwellings or additions to dwellings sited up to shared property boundaries (e.g. additions to a semi-detached dwelling or terraced dwellings);
- excavations for new dwellings, additions to dwellings, swimming pools or other substantial structures which are within rock and may result in vibration and or potential damage to any dwelling, associated garage or other substantial structure located upon an adjoining premises;
- as otherwise may be required by the *Principal Certifying Authority*.

The dilapidation report shall include details of the current condition and status of any dwelling, associated garage or other substantial structure located upon the adjoining premises and shall include relevant photographs of the structures, to the satisfaction of the *Principal Certifying Authority*.

The dilapidation report must be submitted to the Council, the *Principal Certifying Authority* and the owners of the adjoining/nearby premises encompassed in the report, prior to commencing any site works (including any demolition work, excavation work or building work).

Construction Noise & Vibration Management Plan

22. Noise and vibration emissions during the construction of the building and associated site works must not result in damage to nearby premises or result in an unreasonable loss of amenity to nearby residents and the relevant requirements of the *Protection of the Environment Operations Act 1997* and NSW EPA Guidelines must be satisfied at all times.

Noise and vibration from any rock excavation machinery, pile drivers and all plant and equipment must be minimised, by using appropriate plant and equipment, silencers and the implementation of noise management strategies.

A *Construction Noise Management Plan*, prepared in accordance with the NSW EPA Construction Noise Guideline by a suitably qualified person, is to be

implemented throughout the works, to the satisfaction of the Council. A copy of the strategy must be provided to the Principal Certifying Authority and Council prior to the commencement of works on site.

Construction Site Management Plan

23. A *Construction Site Management Plan* must be developed and implemented prior to the commencement of any works. The construction site management plan must include the following measures, as applicable to the type of development:

- location and construction of protective site fencing / hoardings;
- location of site storage areas/sheds/equipment;
- location of building materials for construction;
- provisions for public safety;
- dust control measures;
- details of proposed sediment and erosion control measures;
- site access location and construction
- details of methods of disposal of demolition materials;
- protective measures for tree preservation;
- location and size of waste containers/bulk bins;
- provisions for temporary stormwater drainage;
- construction noise and vibration management;
- construction traffic management details;
- provisions for temporary sanitary facilities.

The site management measures must be implemented prior to the commencement of any site works and be maintained throughout the works, to the satisfaction of Council.

A copy of the Construction Site Management Plan must be provided to the Principal Certifying Authority and Council prior to commencing site works. A copy must also be maintained on site and be made available to Council officers upon request.

Demolition & Construction Waste

24. A *Demolition and Construction Waste Management Plan* (WMP) must be developed and implemented for the development.

The Waste Management Plan must provide details of the type and quantities of demolition and construction waste materials, proposed re-use and recycling of materials, methods of disposal and details of recycling outlets and land fill sites. Where practicable waste materials must be re-used or recycled, rather than disposed and further details of Council's requirements including relevant guidelines and pro-forma WMP forms can be obtained from Council's Customer Service Centre or by telephoning Council on 1300 722 542.

Details and receipts verifying the recycling and disposal of materials must be kept on site at all times and presented to Council officers upon request.

Public Utilities

25. A *Public Utility Impact Assessment* must be carried out to identify all public utility services located on the site, roadway, nature strip, footpath, public reserve or any public areas associated with and/or adjacent to the building works. The assessment should include relevant information from public utility authorities and exploratory trenching or pot-holing, if necessary, to determine the position and level of services.

Documentary evidence from the relevant public utility authorities confirming that their requirements have been or are able to be satisfied, must be submitted to the Principal Certifying Authority prior to the commencement of any demolition, excavation or building works.

26. The owner/builder must make the necessary arrangements and meet the full cost for telecommunication companies, gas providers, Ausgrid, Sydney Water and other authorities to adjust, repair or relocate their services as required.

Underground Power Feed Connection

27. The existing overhead power feed between the Power Pole located on the same side of the street, opposite the southern side boundary, shall be relocated to an underground (UGOH) connection from the subject Power Pole.

The applicant/owner is to liaise with an Ausgrid Accredited Service Provider to carry out the works to the requirements and satisfaction of Ausgrid and at no cost to Council.

REQUIREMENTS DURING CONSTRUCTION & SITE WORK

The following conditions of consent must be complied with during the demolition, excavation and construction of the development.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of public health, safety and environmental amenity during construction.

Inspections during Construction

28. Building works are required to be inspected by the *Principal Certifying Authority*, in accordance with section 6.5 of the *Environmental Planning & Assessment Act 1979* and clause 162A of the *Environmental Planning & Assessment Regulation 2000*, to monitor compliance with the relevant standards of construction, Council’s development consent and the construction certificate.

Site Signage

29. A sign must be erected and maintained in a prominent position on the site for the duration of the works, which contains the following details:
- name, address, contractor licence number and telephone number of the principal contractor, including a telephone number at which the person may be contacted outside working hours, or owner-builder permit details (as applicable)
 - name, address and telephone number of the Principal Certifying Authority,
 - a statement stating that “unauthorised entry to the work site is prohibited”.

Restriction on Working Hours

30. Building, demolition and associated site works must be carried out in accordance with the following requirements:

Activity	Permitted working hours
All building, demolition and site work, including site deliveries (except as detailed below)	<ul style="list-style-type: none"> • Monday to Friday - 7.00am to 5.00pm • Saturday - 8.00am to 5.00pm • Sunday & public holidays - No work permitted
Excavating or sawing of rock, use of jack-hammers, pile-drivers,	<ul style="list-style-type: none"> • Monday to Friday - 8.00am to 5.00pm • Saturday - No work permitted

vibratory rollers/compactors or the like	<ul style="list-style-type: none"> • Sunday & public holidays - No work permitted
--	--

An application to vary the abovementioned hours may be submitted to Council's Manager Health, Building & Regulatory Services for consideration and approval to vary the specified hours may be granted in exceptional circumstances and for limited occasions (e.g. for public safety, traffic management or road safety reasons). Any applications are to be made on the standard application form and include payment of the relevant fees and supporting information. Applications must be made at least 10 days prior to the date of the proposed work and the prior written approval of Council must be obtained to vary the standard permitted working hours.

Removal of Asbestos Materials

31. Any work involving the demolition, storage or disposal of asbestos products and materials must be carried out in accordance with the following requirements:

- Occupational Health & Safety legislation and WorkCover NSW requirements
- Randwick City Council's Asbestos Policy
- A WorkCover licensed demolition or asbestos removal contractor must undertake removal of more than 10m² of bonded asbestos (or as otherwise specified by WorkCover or relevant legislation). Removal of friable asbestos material must only be undertaken by contractor that holds a current friable asbestos removal licence. A copy of the relevant licence must be provided to the Principal Certifying Authority.
- On sites involving the removal of asbestos, a sign must be clearly displayed in a prominent visible position at the front of the site, containing the words 'DANGER ASBESTOS REMOVAL IN PROGRESS' and include details of the licensed contractor.
- Asbestos waste must be stored, transported and disposed of in compliance with the *Protection of the Environment Operations Act 1997* and the *Protection of the Environment Operations (Waste) Regulation 2005*. Details of the landfill site (which must be lawfully able to receive asbestos materials) must be provided to the Principal Certifying Authority.
- A Clearance Certificate or Statement, prepared by a suitably qualified person (i.e. an occupational hygienist, licensed asbestos assessor or other competent person), must be provided to Council and the Principal certifying authority upon completion of the asbestos related works which confirms that the asbestos material have been removed appropriately and the relevant conditions of consent have been satisfied.

A copy of Council's Asbestos Policy is available on Council's web site at www.randwick.nsw.gov.au in the Building & Development Section or a copy can be obtained from Council's Customer Service Centre.

Excavations, Back-filling & Retaining Walls

32. All excavations and backfilling associated with the erection or demolition of a building must be executed safely in accordance with appropriate professional standards and excavations must be properly guarded and supported to prevent them from being dangerous to life, property or buildings.

Retaining walls, shoring or piling must be provided to support land which is excavated in association with the erection or demolition of a building, to prevent the movement of soil and to support the adjacent land and buildings, if the soil conditions require it. Adequate provisions are also to be made for drainage.

Details of proposed retaining walls, shoring, piling or other measures are to be submitted to and approved by the Principal Certifying Authority.

Support of Adjoining Land

33. In accordance with section 4.17 (11) of the *Environmental Planning & Assessment Act 1979* and clause 98 E of the *Environmental Planning & Assessment Regulation 2000*, it is a prescribed condition that the adjoining land and buildings located upon the adjoining land must be adequately supported at all times.
34. Prior to undertaking any demolition, excavation or building work in the following circumstances, a report must be obtained from a *professional engineer* which details the methods of support for the dwelling or associated structure on the adjoining land, to the satisfaction of the *Principal Certifying Authority*:
- when undertaking excavation or building work within the zone of influence of the footings of a dwelling or associated structure that is located on the adjoining land;
 - when undertaking demolition work to a wall of a dwelling that is built to a common or shared boundary (e.g. semi-detached or terrace dwelling);
 - when constructing a wall to a dwelling or associated structure that is located within 900mm of a dwelling located on the adjoining land;
 - as may be required by the *Principal Certifying Authority*.

The demolition, excavation and building work and the provision of support to the dwelling or associated structure on the adjoining land, must also be carried out in accordance with the abovementioned report, to the satisfaction of the *Principal Certifying Authority*.

Sediment & Erosion Control

35. Sediment and erosion control measures, must be implemented throughout the site works in accordance with the manual for Managing Urban Stormwater – Soils and Construction, published by Landcom.

Details of the sediment and erosion control measures to be implemented on the site must be included in with the Construction Management Plan and be provided to the Principal Certifying Authority and Council. A copy must also be maintained on site and be made available to Council officers upon request.

Public Safety & Site Management

36. Public safety and convenience must be maintained at all times during demolition, excavation and construction works and the following requirements must be complied with:
- a) Public access to the building site and materials must be restricted by existing boundary fencing or temporary site fencing having a minimum height of 1.5m, to Council's satisfaction.

Temporary site fences are required to be constructed of cyclone wire fencing material and be structurally adequate, safe and constructed in a professional manner. The use of poor quality materials or steel reinforcement mesh as fencing is not permissible.

- b) Building materials, sand, soil, waste materials, construction equipment or other articles must not be placed upon the footpath, roadway or nature strip at any time.
- c) The road, footpath, vehicular crossing and nature strip must be maintained in a good, safe, clean condition and free from any excavations, obstructions, trip hazards, goods, materials, soils or debris at all times. Any damage caused to the road, footway, vehicular crossing, nature strip or any public place must be repaired immediately, to the satisfaction of Council.
- d) All building and site activities (including storage or placement of materials or waste and concrete mixing/pouring/pumping activities) must not cause or be likely to cause 'pollution' of any waters, including any stormwater drainage systems, street gutters or roadways.

Note: It is an offence under the Protection of the Environment Operations Act 1997 to cause or be likely to cause 'pollution of waters', which may result in significant penalties and fines.

- e) Access gates and doorways within site fencing, hoardings and temporary site buildings or amenities must not open out into the road or footway.
- f) Site fencing, building materials, bulk bins/waste containers and other articles must not be located upon the footpath, roadway or nature strip at any time without the prior written approval of the Council. Applications to place a waste container in a public place can be made to Council's Health, Building and Regulatory Services department.
- g) Adequate provisions must be made to ensure pedestrian safety and traffic flow during the site works and traffic control measures are to be implemented in accordance with the relevant provisions of the Roads and Traffic Manual "Traffic Control at Work Sites" (Version 4), to the satisfaction of Council.
- h) A Road / Asset Opening Permit must be obtained from Council prior to carrying out any works within or upon a road, footpath, nature strip or in any public place, in accordance with section 138 of the *Roads Act 1993* and all of the conditions and requirements contained in the Road / Asset Opening Permit must be complied with. Please contact Council's Road/Asset Openings officer on 9093 6691 for further details.
- i) Temporary toilet facilities are to be provided, at or in the vicinity of the work site throughout the course of demolition and construction, to the satisfaction of WorkCover NSW and the toilet facilities must be connected to a public sewer or other sewage management facility approved by Council.

Site Signage

37. A sign must be erected and maintained in a prominent position on the site for the duration of the works, which contains the following details:

- name, address, contractor licence number and telephone number of the *principal contractor*, including a telephone number at which the person may be contacted outside working hours, or *owner-builder* permit details (as applicable)
- name, address and telephone number of the *Principal Certifying Authority*,
- a statement stating that "unauthorised entry to the work site is prohibited".

Survey Requirements

38. A Registered Surveyor's check survey certificate or other suitable documentation must be obtained at the following stage/s of construction to demonstrate compliance with the approved setbacks, levels, layout and height of the building to the satisfaction of the Principal Certifying Authority (PCA):
- prior to construction (pouring of concrete) of the footings or first completed floor slab,
 - upon completion of the building, prior to issuing an occupation certificate,
 - as otherwise may be required by the PCA.

The survey documentation must be forwarded to the Principal Certifying Authority and a copy is to be forwarded to the Council, if the Council is not the Principal Certifying Authority for the development.

Building Encroachments

39. There must be no encroachment of any structures or building work onto Council's road reserve, footway, nature strip or public place.

Road/Asset Opening Permit

40. Any openings within or upon the road, footpath, nature strip or in any public place (i.e. for proposed drainage works or installation of services), must be carried out in accordance with the following requirements, to the satisfaction of Council:

- A *Road / Asset Opening Permit* must be obtained from Council prior to carrying out any works within or upon a road, footpath, nature strip or in any public place, in accordance with section 138 of the *Roads Act 1993* and all of the conditions and requirements contained in the *Road / Asset Opening Permit* must be complied with.
- The owner/builder must ensure that all works within or upon the road reserve, footpath, nature strip or other public place are completed to the satisfaction of Council, prior to the issuing of a *final occupation certificate* for the development.
- Relevant *Road / Asset Opening Permit* fees, repair fees, inspection fees and security deposits, must be paid to Council prior to commencing any works within or upon the road, footpath, nature strip or other public place.

For further information, please contact Council's Road / Asset Opening Officer on 1300 722 542.

Tree Management

41. Approval is granted for removal of the following vegetation from within the subject site so as to accommodate works in these same areas as shown, subject to full implementation of the approved landscaping:
- a) The *Jacaranda mimosifolia* (Jacaranda, T2) located centrally in the front setback, as despite being the dominant specimen in this area, is only in fair health and condition due to a combination of past damage/wounds, deadwood and dieback, which has arisen due to its poor/restricted growing environment, comprising existing impervious pavers, a rockery garden, and brick boundary walls;
 - b) The *Metrosideros excelsa* (Pohutakawa, T3) immediately to its north, on the northern boundary, as it is a low value, short-lived exotic species;
 - c) The row of four *Cupressus torulosa* (Bhutan Cypress, T5-8) further to the west, hard up against the northern brick wall/fence, as despite being mature, are all in poor condition as all lower growing branches and foliage

- have already been removed, and will never grow back, with major demolition and excavation works also shown for this same area;
- d) The *Magnolia lilliflora* (Saucer Magnolia, T4) to their south, as it is insignificant and in direct conflict with all works.

Pruning of neighbours trees

42. Permission is granted for the minimal and selective pruning of only those lower growing branches from the row of trees that are located wholly on the adjoining private property to the south, no.98, hard up against the common boundary/existing brick fence, only where they overhang into the subject site and need to be pruned in order to avoid damage to the trees; or; interference with the approved works.
43. This approval does not imply any right of entry onto a neighbouring property nor does it allow pruning beyond a common boundary; however, where such measures are desirable in the best interests of correct pruning procedures, and ultimately, the ongoing health of these trees, the applicant must negotiate with the neighbour/tree owner for access to perform this work.
44. All pruning must be undertaken by an Arborist who holds a minimum of AQF Level III in Arboriculture, and to the requirements of Australian Standard AS 4373-2007 'Pruning of Amenity Trees,' and NSW Work Cover Code of Practice for the Amenity Tree Industry (1998).

REQUIREMENTS PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE

The following conditions of consent must be complied with prior to the 'Principal Certifying Authority' issuing an 'Occupation Certificate'.

Note: For the purpose of this consent, any reference to 'occupation certificate' shall also be taken to mean 'interim occupation certificate' unless otherwise stated.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000*, Council's development consent and to maintain reasonable levels of public health, safety and amenity.

Occupation Certificate Requirements

45. An Occupation Certificate must be obtained from the Principal Certifying Authority prior to any occupation of the building work encompassed in this development consent (including alterations and additions to existing buildings), in accordance with the relevant provisions of the *Environmental Planning & Assessment Act 1979*.

BASIX Requirements & Certification

46. In accordance with Clause 154B of the *Environmental Planning & Assessment Regulation 2000*, a Certifying Authority must not issue an Occupation Certificate for this development, unless it is satisfied that any relevant BASIX commitments and requirements have been satisfied.

Relevant documentary evidence of compliance with the BASIX commitments is to be forwarded to the *Principal Certifying Authority* and Council upon issuing an Occupation Certificate.

Swimming Pool Safety

47. Swimming pools are to be designed and installed in accordance with the relevant requirements of the *Building Code of Australia* and be provided with childproof

fences and self-locking gates, in accordance with the *Swimming Pools Act 1992* and the *Swimming Pools Regulation 2008*.

The swimming pool is to be surrounded by a child-resistant barrier (e.g. fence), that separates the pool from any *residential building* (as defined in the *Swimming Pools Act 1992*) that is situated on the premises and from any place (whether public or private) adjoining the premises; and that is designed, constructed and installed in accordance with Australian Standard AS 1926.1 – 2012 (Swimming Pool Safety Part 1 - Safety Barriers for Swimming Pools).

Gates to pool area must be self-closing and latching at all times and, the gate is required to open outwards from the pool area and prevent a small child opening the gate or door when the gate or door is closed.

Temporary pool safety fencing is to be provided pending the completion of all building work and the pool must not be filled until a fencing inspection has been carried out and approved by the principal certifying authority.

A 'warning notice' must be erected in a prominent position in the immediate vicinity of the swimming pool, in accordance with the provisions of the *Swimming Pools Regulation 2008*, detailing pool safety requirements, resuscitation techniques and the importance of the supervision of children at all times.

Spa Pool Safety

48. Spa pools are to be designed and installed in accordance with the relevant provisions of the *Building Code of Australia* and be provided with a child resistant barrier, in accordance with the provisions of the *Swimming Pools Act 1992* and the *Swimming Pools Regulation 2008*.

A 'warning notice' must be erected in a prominent position in the immediate vicinity of the swimming pool, in accordance with the provisions of the *Swimming Pools Regulation 2008*, detailing pool safety requirements, resuscitation techniques and the importance of the supervision of children at all times.

Swimming Pool & Spa Pool Requirements

49. Swimming pools (and spa pools) are to be designed, installed and operated in accordance with the following general requirements:
- a) Backwash of the pool filter and other discharge of water is to be drained to the sewer in accordance with the requirements of the Sydney Water Corporation; and
 - b) All pool overflow water is to be drained away from the building and adjoining premises, so as not to result in a nuisance or damage to premises; and
 - c) Water recirculation and filtrations systems are required to comply with AS 1926.3 – 2010: Swimming Pool Safety – Water Recirculation and Filtration Systems; and
 - d) Pool plant and equipment is to be enclosed in a sound absorbing enclosure or installed within a building, to minimise noise emissions and possible nuisance to nearby residents.

Notification of Swimming Pools & Spa Pools

50. The owner of the premises must 'register' the swimming pool [or spa pool] on the NSW Swimming Pool Register, in accordance with the *Swimming Pools Act 1992*.

The Swimming Pool Register is administered by the NSW Office of Local Government and registration on the Swimming Pool Register may be made on-line via their website www.swimmingpoolregister.nsw.gov.au.

Registration must be made prior to the issue of an Occupation Certificate for the pool and a copy of the NSW Swimming Pool Certificate of Registration must be forwarded to the Principal Certifying Authority and Council accordingly.

Council's Infrastructure, Vehicular Crossings & Road Openings

51. The owner/developer must meet the full cost for a Council approved contractor to:
- a) Reconstruct the existing Council vehicular crossing and layback, if required, to Council's specifications and requirements.
52. The applicant must meet the full cost for Council or a Council approved contractor to repair/replace any damaged sections of Council's footpath, kerb & gutter, nature strip etc which are due to building works being carried out at the above site. This includes the removal of cement slurry from Council's footpath and roadway.
53. All external civil work to be carried out on Council property (including the installation and repair of roads, footpaths, vehicular crossings, kerb and guttering and drainage works), must be carried out in accordance with Council's "Crossings and Entrances – Contributions Policy" and "Residents' Requests for Special Verge Crossings Policy" and the following requirements:
- a) Details of the proposed civil works to be carried out on Council land must be submitted to Council in a Civil Works Application Form. Council will respond, typically within 4 weeks, with a letter of approval outlining conditions for working on Council land, associated fees and workmanship bonds. Council will also provide details of the approved works including specifications and construction details.
 - b) Works on Council land, must not commence until the written letter of approval has been obtained from Council and heavy construction works within the property are complete. The work must be carried out in accordance with the conditions of development consent, Council's conditions for working on Council land, design details and payment of the fees and bonds outlined in the letter of approval.
 - c) The civil works must be completed in accordance with the above, prior to the issuing of an occupation certificate for the development, or as otherwise approved by Council in writing.

Stormwater Drainage

54. The applicant shall submit to the Principal Certifying Authority (PCA) and Council, certification from a suitably qualified and experienced Hydraulic Engineer confirming that the design and construction of the stormwater drainage system complies with Australian Standard 3500.3:2003 (Plumbing & Drainage-Stormwater Drainage) and the conditions of this development consent.

The certification must be provided following inspection/s of the site stormwater drainage system by the certifying engineers and shall be provided to the satisfaction of the PCA.

55. Should a infiltration area or pump-out system be provided, a works-as-executed drainage plan prepared by a registered surveyor and approved by a suitably qualified and experienced hydraulic consultant/engineer must be forwarded to the Principal Certifying Authority and the Council. The works-as-executed plan must include the following details (as applicable):
- The location, diameter, gradient and material (i.e. PVC, RC etc) of all stormwater pipes;
 - Details of infiltration/absorption systems; and
 - Details of pumping systems installed (including wet well volumes).

Undergrounding of Power

56. Prior to the issuing of any form of Occupation Certificate the existing overhead power feed between the Power Pole located on the same side of the street, opposite the southern side boundary, is to have been relocated to an underground (UGOH) connection from the subject Power Pole.

Landscaping

57. Prior to issuing any Occupation Certificate, certification from a qualified professional in the landscape/horticultural industry must be submitted to, and be approved by, the PCA, confirming the date that the completed landscaping was inspected, and that it has been installed substantially in accordance with the Lower Ground, Ground & First Floor Landscape Plans by Secret Gardens, dwg's DA-01 – 02, rev B, dated 08/08/18.
58. Suitable strategies shall be implemented to ensure that the landscaping is maintained in a healthy and vigorous state until maturity, for the life of the development.
59. The nature-strip upon Council's footway shall be re-graded and re-turfed with Kikuyu Turf rolls, including turf underlay, wholly at the applicant's cost, to Council's satisfaction, prior to the issue of any Occupation Certificate.

Street and/or Sub-Address Numbering

60. Street numbering must be provided to the front of the premises in a prominent position, in accordance with the Australia Post guidelines and AS/NZS 4819 (2003) to the satisfaction of Council.

If this application results in an additional lot, dwelling or unit, an application must be submitted to and approved by Council's Director of City Planning, together with the required fee, for the allocation of appropriate street and/or unit numbers for the development. The street and/or unit numbers must be allocated prior to the issue of an occupation certificate.

Please note: any Street or Sub-Address Numbering provided by an applicant on plans, which have been stamped as approved by Council are not to be interpreted as endorsed, approved by, or to the satisfaction of Council.

<p>OPERATIONAL CONDITIONS</p> <p>The following operational conditions must be complied with at all times, throughout the use and operation of the development.</p>

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979, Environmental Planning & Assessment Regulation 2000*, Council's development consent and to maintain reasonable levels of public health and environmental amenity.

External Lighting

61. External lighting to the premises must be designed and located so as to minimise light-spill beyond the property boundary or cause a public nuisance.

Waste Management

62. Adequate provisions are to be made within the premises for the storage and removal of waste and recyclable materials, to the satisfaction of Council.

Plant & Equipment – Noise Levels

63. The operation of all plant and equipment on the premises shall not give rise to an 'offensive noise' as defined in the Protection of the Environment Operations Act 1997 and Regulations.

In this regard, the operation of the plant and equipment shall not give rise to an LAeq, 15 min sound pressure level at any affected premises that exceeds the background LA90, 15 min noise level, measured in the absence of the noise source/s under consideration by more than 5dB(A) in accordance with relevant NSW Environment Protection Authority (EPA) Noise Control Guidelines.

Swimming/Spa Pools

64. The pool plant and equipment shall not be operated during the following hours if the noise emitted can be heard within a habitable room in any other residential premises, or, as otherwise specified in relevant Noise Control Regulations:

- before 8.00am or after 8.00pm on any Sunday or public holiday; or
- before 7.00am or after 8.00pm on any other day.

Air Conditioners

65. Air conditioning plant and equipment shall not be operated during the following hours if the noise emitted can be heard within a habitable room in any other residential premises, or, as otherwise specified in relevant Noise Control Regulations:

- before 8.00am or after 10.00pm on any Saturday, Sunday or public holiday; or
- before 7.00am or after 10.00pm on any other day.

Rainwater Tanks

66. The operation of plant and equipment associated with rainwater tanks are to be restricted to the following hours if the noise emitted can be heard within a habitable room in any other residential premises:

- before 8.00am or after 8.00pm on weekends or public holiday; or
- before 7.00am or after 8.00pm on weekdays.

Use of parking spaces

67. The car spaces within the development are for the exclusive use of the occupants of the building. The car spaces must not be leased to any person/company that is not an occupant of the building.

Use of first floor

68. The first floor shall not be adapted for use as a separate dwelling.

GENERAL ADVISORY NOTES

The following information is provided for your assistance to ensure compliance with the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000*, or other relevant legislation and requirements. This information does not form part of the conditions of development consent pursuant to Section 4.17 of the Act.

- A1 Underground assets (eg pipes, cables etc) may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial before you dig at www.1100.com.au or telephone on 1100 before excavating or erecting structures (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial before you dig service in advance of any construction or planning activities.
- A2 The applicant is to advise Council in writing and/or photographs of any signs of existing damage to the Council roadway, footway, or verge prior to the commencement of any building/demolition works.
- A3 Further information and details on Council's requirements for trees on development sites can be obtained from the recently adopted Tree Technical Manual, which can be downloaded from Council's website at the following link, <http://www.randwick.nsw.gov.au> - Looking after our environment – Trees – Tree Management Technical Manual; which aims to achieve consistency of approach and compliance with appropriate standards and best practice guidelines.
- A4 The requirements and provisions of the *Environmental Planning & Assessment Act 1979* and *Environmental Planning & Assessment Regulation 2000*, must be fully complied with at all times.

Failure to comply with these requirements is an offence, which renders the responsible person liable to a maximum penalty of \$1.1 million. Alternatively, Council may issue a penalty infringement notice (for up to \$3,000) for each offence. Council may also issue notices and orders to demolish unauthorised or non-complying building work, or to comply with the requirements of Council's development consent.

- A5 In accordance with the requirements of the *Environmental Planning & Assessment Act 1979*, building works, including associated demolition and excavation works (as applicable) must not be commenced until:
- A *Construction Certificate* has been obtained from an Accredited Certifier or Council,
 - An Accredited Certifier or Council has been appointed as the *Principal Certifying Authority* for the development,
 - Council and the Principal Certifying Authority have been given at least 2 days notice (in writing) prior to commencing any works.

A6 Council can issue your *Construction Certificate* and be your *Principal Certifying Authority* for the development, to undertake inspections and ensure compliance with the development consent and relevant building regulations. For further details contact Council on 9093 6944.

A7 This determination does not include an assessment of the proposed works under the Building Code of Australia (BCA) and other relevant Standards. All new building work (including alterations and additions) must comply with the BCA and relevant Standards and you are advised to liaise with your architect, engineer and building consultant prior to lodgement of your construction certificate.

A8 Any proposed amendments to the design and construction of the building may require a new development application or a section 4.55 amendment to the existing consent to be obtained from Council, before carrying out such works

A9 A Local Approval application must be submitted to and be approved by Council prior to commencing any of the following activities on a footpath, road, nature strip or in any public place:-

- Install or erect any site fencing, hoardings or site structures
- Operate a crane or hoist goods or materials over a footpath or road
- Placement of a waste skip or any other container or article.

For further information please contact Council on 9093 6971.

A10 Specific details of the location of the building/s should be provided in the Construction Certificate to demonstrate that the proposed building work will not encroach onto the adjoining properties, Council's road reserve or any public place.

A11 This consent does not authorise any trespass or encroachment upon any adjoining or supported land or building whether private or public. Where any underpinning, shoring, soil anchoring (temporary or permanent) or the like is proposed to be carried out upon any adjoining or supported land, the land owner or principal contractor must obtain:

- the consent of the owners of such adjoining or supported land to trespass or encroach, or
- an access order under the *Access to Neighbouring Land Act 2000*, or
- an easement under section 88K of the *Conveyancing Act 1919*, or
- an easement under section 40 of the *Land & Environment Court Act 1979*, as appropriate.

Section 177 of the *Conveyancing Act 1919* creates a statutory duty of care in relation to support of land. Accordingly, a person has a duty of care not to do anything on or in relation to land being developed (the supporting land) that removes the support provided by the supporting land to any other adjoining land (the supported land).

A12 The finished ground levels external to the building must be consistent with the development consent and are not to be raised, other than for the provision of approved paving or the like on the ground

A13 An application must be submitted to and approved by Council prior to the installation and operation of any proposed greywater or wastewater treatment systems, in accordance with the *Local Government Act 1993*.

Greywater/Wastewater treatment systems must comply with the relevant requirements and guidelines produced by NSW Health, NSW Office of Environment and Heritage and other relevant regulatory requirements.

- A14 Council's assessment of this application does not include an assessment of compliance with the *Swimming Pool Act 1992*. All pool barriers, fences and structures within properties containing a swimming pool must comply with the requirements of the *Swimming Pool Act 1992*, BCA and relevant Australian Standards.

Details of compliance with the *Swimming Pool Act 1992*, Building Code of Australia and relevant Standards must be included in the Construction Certificate to the satisfaction of the Certifying Authority.