

Development Consent Conditions Dwellings



Folder /DA No:	DA/532/2018
Property:	127 Darley Road, RANDWICK NSW 2031
Proposal:	Demolition to existing and construction of a new extension to rear of the dwelling, including internal alterations and additions including new ground floor balcony and lower floor paved terrace area, part demolition of existing rear detached garage and convert to secondary dwelling with new extension, and construction of a new garage.
Recommendation:	Approval

Development Consent Conditions

GENERAL CONDITIONS

The development must be carried out in accordance with the following conditions of consent.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of environmental amenity.

Approved Plans & Supporting Documentation

- The development must be implemented substantially in accordance with the plans and supporting documentation listed below and endorsed with Council's approved stamp, except where amended by Council in red and/or by other conditions of this consent:

Plan	Drawn by	Dated
1805-001	Brooke Aitken Design	July 2018
1805-100	Brooke Aitken Design	July 2018
1805-101	Brooke Aitken Design	July 2018
1805-102	Brooke Aitken Design	July 2018
1805-103	Brooke Aitken Design	July 2018
1805-104	Brooke Aitken Design	July 2018
1805-105	Brooke Aitken Design	July 2018
1805-106	Brooke Aitken Design	July 2018
1805-107	Brooke Aitken Design	July 2018
1805-108	Brooke Aitken Design	July 2018
1805-109	Brooke Aitken Design	July 2018
1805-110	Brooke Aitken Design	July 2018
1805-111	Brooke Aitken Design	July 2018
1805-112	Brooke Aitken Design	July 2018

DA01	Robert Finnie Design	22/8/2018
DA02	Robert Finnie Design	22/8/2018
DA03	Robert Finnie Design	22/8/2018
Materials Board	Received by Council 27/8/2018	

<i>BASIX Certificate No.</i>	<i>Dated</i>
949667S	24/8/2018
A324160	24/8/2018

Amendment of Plans & Documentation

2. The approved plans and documents must be amended in accordance with the following requirements:

- a. A privacy screen having a height of 1.6m (measured above the FFL of the rear, first floor balcony) shall be provided to the western, first floor elevation of the balcony.

Privacy screen/s must be constructed with either:

- Translucent or obscured glazing (The use of film applied to the clear glass pane is unacceptable);
- Fixed lattice/slats with individual openings not more than 30mm wide;
- Fixed vertical or horizontal louvres with the individual blades angled and spaced appropriately to prevent overlooking into the private open space or windows of the adjacent dwellings.

- b. The layout of the bedrooms on ground floor of the existing building shall incorporate 300mm nib walls and beams projecting below ceiling level, as evidence of the original layout of the building and facilitate patching of plasterwork.

- c. A brief archival recording of the property shall be prepared and submitted to and approved by Council's Director City Planning, in accordance with Section 4.17 (2) of the Environmental Planning and Assessment Act 1979 prior to a construction certificate being issued for the development. This recording shall be in accordance with the NSW Heritage Office 2006 Guidelines for Photographic Recording of Heritage Items using Film or Digital Capture. Two copies of the endorsed archival recording shall be presented to Council, one of which shall be placed in the Local History Collection of Randwick City Library.

- d. The ground floor eastern elevation of the garage must be setback 1.2m from the eastern boundary to ensure the visual amenity of No. 129 Darley Road is preserved.

REQUIREMENTS BEFORE A CONSTRUCTION CERTIFICATE CAN BE ISSUED

The following conditions of consent must be complied with before a 'Construction Certificate' is issued by either Randwick City Council or an Accredited Certifier. All necessary information to demonstrate compliance with the following conditions of consent must be included in the documentation for the construction certificate.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000*, Council's development consent conditions and to achieve reasonable levels of environmental amenity.

Consent Requirements

3. The requirements and amendments detailed in the 'General Conditions' must be complied with and be included in the construction certificate plans and associated documentation.

Section 7.12 Development Contributions

4. In accordance with Council's Development Contributions Plan effective from 21 April 2015, based on the development cost of \$1,593,326.99 the following applicable monetary levy must be paid to Council: \$15,933.25.

The levy must be paid in **cash, bank cheque** or by **credit card** prior to a construction certificate being issued for the proposed development. The development is subject to an index to reflect quarterly variations in the Consumer Price Index (CPI) from the date of Council's determination to the date of payment. Please contact Council on telephone 9093 6999 or 1300 722 542 for the indexed contribution amount prior to payment.

To calculate the indexed levy, the following formula must be used:

$$\mathbf{IDC = ODC \times CP2/CP1}$$

Where:

IDC = the indexed development cost

ODC = the original development cost determined by the Council

CP2 = the Consumer Price Index, All Groups, Sydney, as published by the ABS in respect of the quarter ending immediately prior to the date of payment

CP1 = the Consumer Price Index, All Groups, Sydney as published by the ABS in respect of the quarter ending immediately prior to the date of imposition of the condition requiring payment of the levy.

Council's Development Contribution Plans may be inspected at the Customer Service Centre, Administrative Centre, 30 Frances Street, Randwick or at www.randwick.nsw.gov.au.

Compliance Fee

5. A development compliance and enforcement fee of \$1,593.35 shall be paid to Council in accordance with Council's adopted Fees & Charges Pricing Policy, prior to the issue of a Construction Certificate for development.

Long Service Levy Payments

6. The required Long Service Levy payment, under the *Building and Construction Industry Long Service Payments Act 1986*, must be forwarded to the Long Service Levy Corporation or the Council, in accordance with Section 6.8 of the *Environmental Planning & Assessment Act 1979*.

At the time of this development consent, Long Service Levy payment is applicable on building work having a value of \$25,000 or more, at the rate of 0.35% of the cost of the works.

Sydney Water Requirements

7. All building, plumbing and drainage work must be carried out in accordance with the requirements of the Sydney Water Corporation.

The approved plans must be submitted to the Sydney Water **Tap in™** online service, to determine whether the development will affect Sydney Water's waste water and water mains, stormwater drains and/or easements, and if any further requirements need to be met.

*The Sydney Water **Tap in™** online service replaces the Quick Check Agents as of 30 November 2015*

The **Tap in™** service provides 24/7 access to a range of services, including:

- Building plan approvals
- Connection and disconnection approvals
- Diagrams
- Trade waste approvals
- Pressure information
- Water meter installations
- Pressure boosting and pump approvals
- Change to an existing service or asset, e.g. relocating or moving an asset.

Sydney Water's **Tap in™** online service is available at:
<https://www.sydneywater.com.au/SW/plumbing-building-developing/building/sydney-water-tap-in/index.htm>

The Principal Certifying Authority must ensure that the developer/owner has submitted the approved plans to Sydney Water Tap in online service.

Stormwater Drainage

8. Surface water/stormwater from the redeveloped site must be drained and discharged to the street gutter or suitably designed absorption pit, to the satisfaction of the Certifying Authority and details are to be included in the construction certificate application for the development.

Absorption pits or soaker wells should be located not less than 3m from any adjoining premises and the stormwater must not be directed to any adjoining premises or cause a nuisance.

Landscape Plans

9. The Certifying Authority/PCA must ensure that the Landscape Plans submitted as part of the approved Construction Certificate are substantially consistent with the Landscape Plans by Robert Finnie Design, dwg's DA01-03, rev A, dated 22/08/18.

Tree Protection Measures

10. In order to ensure retention of the mature *Schinus areira* (Peppercorn) located centrally in the rear yard of the subject site in good health as shown, the following measures are to be undertaken:
- a. All documentation submitted for the Construction Certificate application must show its retention, with the position and diameter of both its trunk and canopy to be clearly and accurately shown on all plans in relation to the proposed works.
 - b. Any excavations associated with the installation of new services, pipes, stormwater systems or similar in the rear yard must be setback a minimum radius of **3 metres** from its trunk (measured off its outside edge at ground level), with the Certifying Authority/PCA to ensure that the Site Drainage Plan by AB Consulting Engineers, dwg D01, issue A, dated 07/08/18 is amended so that the infiltration trench and associated works that are currently shown in this same area comply with this requirement.
 - c. All Construction Certificate plans must also show that the layout and extent of works in the rear yard will be consistent with what is shown on the Lower Floor plan, dwg 1805-00-2, rev A.
 - d. This tree is to be physically protected by the installation of 1.8 metre high steel mesh/chainwire fencing, which shall be located a minimum distance of **2.5 metres** on four sides (measured off the outside edge of its trunk at ground level), to completely enclose this tree for the duration of works.
 - e. This fencing shall be installed prior to the commencement of demolition and construction works and shall remain in place until all works are completed, to which, signage containing the following words shall be clearly displayed and permanently attached: "TREE PROTECTION ZONE (TPZ), DO NOT REMOVE/ENTER".
 - f. In order to prevent soil/sediment being washed over its root system, erosion control measures must be provided at ground level around the perimeter of the TPZ.
 - g. Ground levels within its TPZ must not be altered by more than 200mm, with no other structures such as continuous strip footings, planter boxes or similar to be located in this area, and must remain as undisturbed, deep soil.
 - h. Within the TPZ, there is to be no storage of materials, machinery or site office/sheds, nor is cement to be mixed or chemicals spilt/disposed of and no stockpiling of soil or rubble, with all Site Management Plans needing to acknowledge these requirements.
 - i. Where roots are encountered which are in direct conflict with the approved works, they may be cut cleanly by hand (using only hand held tools, not machinery), with the affected area to be backfilled with clean site soil as soon as practically possible.
 - j. The PCA must ensure compliance with all of these requirements, both on the plans as well as on-site during the course of construction, and prior to issuing any type of Occupation Certificate.

REQUIREMENTS TO BE INCLUDED IN THE CONSTRUCTION CERTIFICATE

The requirements contained in the following conditions of consent must be complied with and details of compliance must be included in the construction certificate for the development.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000*, Councils development consent conditions and to achieve reasonable levels of environmental amenity.

Compliance with the Building Code of Australia & Relevant Standards

11. In accordance with section 4.17 (11) of the *Environmental Planning & Assessment Act 1979* and clause 98 of the *Environmental Planning & Assessment Regulation 2000*, it is a *prescribed condition* that all building work must be carried out in accordance with the provisions of the Building Code of Australia (BCA).

BASIX Requirements

12. In accordance with section 4.17 (11) of the *Environmental Planning & Assessment Act 1979* and clause 97A of the *Environmental Planning & Assessment Regulation 2000*, the requirements and commitments contained in the relevant BASIX Certificate must be complied with.

The required commitments listed and identified in the BASIX Certificate must be included on the construction certificate plans, specifications and associated documentation, to the satisfaction of the Certifying Authority.

The design of the building must not be inconsistent with the development consent and any proposed variations to the building to achieve the BASIX commitments may necessitate a new development consent or amendment to the existing consent to be obtained, prior to a construction certificate being issued.

Stormwater Drainage

13. A surface water/stormwater drainage system must be provided in accordance with the following requirements, to the satisfaction of the Certifying Authority and details are to be included in the construction certificate:-
 - a) Surface water/stormwater drainage systems must be provided in accordance with the relevant provisions of the Building Code of Australia (Volume 2) and relevant Standards;
 - b) The surface water/stormwater must be drained and discharged to the street gutter or, subject to site suitability, the stormwater may be drained to a suitably designed absorption pit;
 - c) Any absorption pits or soaker wells should be located not less than 3m from any adjoining premises and the stormwater must not be directed to any adjoining premises or cause a nuisance;
 - d) External paths and ground surfaces are to be constructed at appropriate levels and be graded and drained away from the building and adjoining premises, so as not to result in the entry of water into the building, or cause a nuisance or damage to the adjoining premises;

- e) Details of any proposed drainage systems or works to be carried out in the road, footpath or nature strip must be submitted to and approved by Council before commencing these works:
- f) A certificate, from a suitably qualified person must be submitted to the PCA and Council, prior to the issue of an Occupation Certificate, which confirms that the stormwater drainage system has been provided in accordance with the requirements of this consent, relevant standards and requirements.

REQUIREMENTS PRIOR TO THE COMMENCEMENT OF ANY WORKS

The following conditions of consent must be complied with prior to the commencement of any works on the site. The necessary documentation and information must be provided to the Council or the '*Principal Certifying Authority*', as applicable.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of public health, safety and environmental amenity.

Certification and Building Inspection Requirements

14. Prior to the commencement of any building works, the following requirements must be complied with:
 - a) a Construction Certificate must be obtained from the Council or an accredited certifier, in accordance with the provisions of the *Environmental Planning & Assessment Act 1979*.

A copy of the construction certificate, the approved development consent plans and consent conditions must be kept on the site at all times and be made available to the Council officers and all building contractors for assessment.
 - b) a *Principal Certifying Authority* (PCA) must be appointed to carry out the necessary building inspections and to issue an *occupation certificate*; and
 - c) a *principal contractor* must be appointed for the building work, or in relation to residential building work, an *owner-builder* permit may be obtained in accordance with the requirements of the *Home Building Act 1989*, and the PCA and Council are to be notified accordingly; and
 - d) the *principal contractor* must be advised of the required *critical stage inspections* and other inspections to be carried out, as specified by the *Principal Certifying Authority*; and
 - e) at least two days notice must be given to the Council, in writing, prior to commencing any works.

Home Building Act 1989

15. In accordance with section 4.17 (11) of the Environmental Planning & Assessment Act 1979 and clause 98 of the Environmental Planning & Assessment Regulation 2000, the relevant requirements of the Home Building Act 1989 must be complied with.

Details of the Licensed Building Contractor and a copy of the relevant Certificate of Home Warranty Insurance or a copy of the Owner-Builder Permit (as applicable) must be provided to the Principal Certifying Authority and Council.

Demolition Work

16. Demolition Work must be carried out in accordance with Australian Standard AS2601-2001, Demolition of Structures and relevant work health and safety requirements.

A Demolition Work Plan must be prepared for the demolition works which should be submitted to the Principal Certifying Authority (PCA), not less than two (2) working days before commencing any demolition work. A copy of the Demolition Work Plan must be maintained on site and be made available to Council officers upon request.

If the work involves asbestos products or materials, a copy of the Demolition Work Plan must also be provided to Council not less than 2 days before commencing those works.

Public Utilities

17. A *Public Utility Impact Assessment* must be carried out on all public utility services on the site, roadway, nature strip, footpath, public reserve or any public areas associated with and/or adjacent to the development/building works and include relevant information from public utility authorities and exploratory trenching or pot-holing, if necessary, to determine the position and level of service.
18. The applicant must meet the full cost for telecommunication companies, gas providers, Ausgrid, and Sydney Water to adjust/repair/relocate their services as required. The applicant must make the necessary arrangements with the service authority.

REQUIREMENTS DURING CONSTRUCTION & SITE WORK

The following conditions of consent must be complied with during the demolition, excavation and construction of the development.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000* and to provide reasonable levels of public health, safety and environmental amenity during construction.

Inspections during Construction

19. Building works are required to be inspected by the *Principal Certifying Authority*, in accordance with section 6.5 of the *Environmental Planning & Assessment Act 1979* and clause 162A of the *Environmental Planning & Assessment Regulation 2000*, to monitor compliance with the relevant standards of construction, Council's development consent and the construction certificate.

Site Signage

20. A sign must be erected and maintained in a prominent position on the site for the duration of the works, which contains the following details:
- name, address, contractor licence number and telephone number of the principal contractor, including a telephone number at which the person may be contacted outside working hours, or owner-builder permit details (as applicable)
 - name, address and telephone number of the Principal Certifying Authority,
 - a statement stating that "unauthorised entry to the work site is prohibited".

Restriction on Working Hours

21. Building, demolition and associated site works must be carried out in accordance with the following requirements:

Activity	Permitted working hours
All building, demolition and site work, including site deliveries (except as detailed below)	<ul style="list-style-type: none">• Monday to Friday - 7.00am to 5.00pm• Saturday - 8.00am to 5.00pm• Sunday & public holidays - No work permitted
Excavating or sawing of rock, use of jack-hammers, pile-drivers, vibratory rollers/compactors or the like	<ul style="list-style-type: none">• Monday to Friday - 8.00am to 5.00pm• Saturday - No work permitted• Sunday & public holidays - No work permitted

An application to vary the abovementioned hours may be submitted to Council's Manager Health, Building & Regulatory Services for consideration and approval to vary the specified hours may be granted in exceptional circumstances and for limited occasions (e.g. for public safety, traffic management or road safety reasons). Any applications are to be made on the standard application form and include payment of the relevant fees and supporting information. Applications must be made at least 10 days prior to the date of the proposed work and the prior written approval of Council must be obtained to vary the standard permitted working hours.

Removal of Asbestos Materials

22. Any work involving the demolition, storage or disposal of asbestos products and materials must be carried out in accordance with the following requirements:
- Occupational Health & Safety legislation and WorkCover NSW requirements
 - Randwick City Council's Asbestos Policy
 - A WorkCover licensed demolition or asbestos removal contractor must undertake removal of more than 10m² of bonded asbestos (or as otherwise specified by WorkCover or relevant legislation). Removal of friable asbestos material must only be undertaken by contractor that holds a current friable asbestos removal licence. A copy of the relevant licence must be provided to the Principal Certifying Authority.
 - On sites involving the removal of asbestos, a sign must be clearly displayed in a prominent visible position at the front of the site, containing the words

'DANGER ASBESTOS REMOVAL IN PROGRESS' and include details of the licensed contractor.

- Asbestos waste must be stored, transported and disposed of in compliance with the *Protection of the Environment Operations Act 1997* and the *Protection of the Environment Operations (Waste) Regulation 2005*. Details of the landfill site (which must be lawfully able to receive asbestos materials) must be provided to the Principal Certifying Authority.
- A Clearance Certificate or Statement, prepared by a suitably qualified person (i.e. an occupational hygienist, licensed asbestos assessor or other competent person), must be provided to Council and the Principal certifying authority upon completion of the asbestos related works which confirms that the asbestos material have been removed appropriately and the relevant conditions of consent have been satisfied.

A copy of Council's Asbestos Policy is available on Council's web site at www.randwick.nsw.gov.au in the Building & Development Section or a copy can be obtained from Council's Customer Service Centre.

Support of Adjoining Land

23. In accordance with section 4.17 (11) of the *Environmental Planning & Assessment Act 1979* and clause 98 E of the *Environmental Planning & Assessment Regulation 2000*, it is a prescribed condition that the adjoining land and buildings located upon the adjoining land must be adequately supported at all times.
24. Prior to undertaking any demolition, excavation or building work in the following circumstances, a report must be obtained from a *professional engineer* which details the methods of support for the dwelling or associated structure on the adjoining land, to the satisfaction of the *Principal Certifying Authority*:
 - when undertaking excavation or building work within the zone of influence of the footings of a dwelling or associated structure that is located on the adjoining land;
 - when undertaking demolition work to a wall of a dwelling that is built to a common or shared boundary (e.g. semi-detached or terrace dwelling);
 - when constructing a wall to a dwelling or associated structure that is located within 900mm of a dwelling located on the adjoining land;
 - as may be required by the *Principal Certifying Authority*.

The demolition, excavation and building work and the provision of support to the dwelling or associated structure on the adjoining land, must also be carried out in accordance with the abovementioned report, to the satisfaction of the *Principal Certifying Authority*.

Sediment & Erosion Control

25. Sediment and erosion control measures, must be implemented throughout the site works in accordance with the manual for Managing Urban Stormwater – Soils and Construction, published by Landcom.

Details of the sediment and erosion control measures to be implemented on the site must be included in with the Construction Management Plan and be provided to the Principal Certifying Authority and Council. A copy must also be maintained on site and be made available to Council officers upon request.

Public Safety & Site Management

26. Public safety and convenience must be maintained at all times during demolition, excavation and construction works and the following requirements must be complied with:

- a) Public access to the building site and materials must be restricted by existing boundary fencing or temporary site fencing having a minimum height of 1.5m, to Council's satisfaction.

Temporary site fences are required to be constructed of cyclone wire fencing material and be structurally adequate, safe and constructed in a professional manner. The use of poor quality materials or steel reinforcement mesh as fencing is not permissible.

- b) Building materials, sand, soil, waste materials, construction equipment or other articles must not be placed upon the footpath, roadway or nature strip at any time.
- c) The road, footpath, vehicular crossing and nature strip must be maintained in a good, safe, clean condition and free from any excavations, obstructions, trip hazards, goods, materials, soils or debris at all times. Any damage caused to the road, footway, vehicular crossing, nature strip or any public place must be repaired immediately, to the satisfaction of Council.
- d) All building and site activities (including storage or placement of materials or waste and concrete mixing/pouring/pumping activities) must not cause or be likely to cause 'pollution' of any waters, including any stormwater drainage systems, street gutters or roadways.

Note: It is an offence under the Protection of the Environment Operations Act 1997 to cause or be likely to cause 'pollution of waters', which may result in significant penalties and fines.

- e) Access gates and doorways within site fencing, hoardings and temporary site buildings or amenities must not open out into the road or footway.
- f) Site fencing, building materials, bulk bins/waste containers and other articles must not be located upon the footpath, roadway or nature strip at any time without the prior written approval of the Council. Applications to place a waste container in a public place can be made to Council's Health, Building and Regulatory Services department.
- g) Adequate provisions must be made to ensure pedestrian safety and traffic flow during the site works and traffic control measures are to be implemented in accordance with the relevant provisions of the Roads and Traffic Manual "Traffic Control at Work Sites" (Version 4), to the satisfaction of Council.
- h) A Road / Asset Opening Permit must be obtained from Council prior to carrying out any works within or upon a road, footpath, nature strip or in any public place, in accordance with section 138 of the *Roads Act 1993* and all of the conditions and requirements contained in the Road / Asset Opening Permit must be complied with. Please contact Council's Road/Asset Openings officer on 9093 6691 for further details.

- i) Temporary toilet facilities are to be provided, at or in the vicinity of the work site throughout the course of demolition and construction, to the satisfaction of WorkCover NSW and the toilet facilities must be connected to a public sewer or other sewage management facility approved by Council.

Site Signage

27. A sign must be erected and maintained in a prominent position on the site for the duration of the works, which contains the following details:
- name, address, contractor licence number and telephone number of the *principal contractor*, including a telephone number at which the person may be contacted outside working hours, or *owner-builder* permit details (as applicable)
 - name, address and telephone number of the *Principal Certifying Authority*,
 - a statement stating that "unauthorised entry to the work site is prohibited".

Tree Management

28. Approval is granted for removal of the stand of Yucca's in the rear yard of the subject site, between the southeast corner of the existing dwelling and awning, so as to accommodate works associated with the new garage, paved terrace, landscaping and detached building in this same area as shown.

Pruning

29. Permission is granted for the minimal and selective pruning of only those lower growing, lower order branches from the *Schinus areira* (Peppercorn) that is located centrally in the rear yard, only where needed to improve/facilitate access during the course of the approved works; or; to avoid damage to the tree.
30. All pruning must be undertaken by an Arborist who holds a minimum of AQF Level III in Arboriculture, and to the requirements of Australian Standard AS 4373-2007 'Pruning of Amenity Trees,' and NSW Work Cover Code of Practice for the Amenity Tree Industry (1998).

Road / Asset Opening Permit

31. A Road / Asset Opening Permit must be obtained from Council prior to carrying out any works within or upon a road, footpath, nature strip or in any public place, in accordance with section 138 of the Roads Act 1993 and all of the conditions and requirements contained in the Road / Asset Opening Permit must be complied with.

The owner/builder must ensure that all works within or upon the road reserve, footpath, nature strip or other public place are completed to the satisfaction of Council, prior to the issuing of a final occupation certificate for the development.

For further information, please contact Council's Road / Asset Opening Officer on 9093 6691 or 1300 722 542.

REQUIREMENTS PRIOR TO THE ISSUE OF AN OCCUPATION CERTIFICATE

The following conditions of consent must be complied with prior to the 'Principal Certifying Authority' issuing an 'Occupation Certificate'.

Note: For the purpose of this consent, any reference to 'occupation certificate' shall also be taken to mean 'interim occupation certificate' unless otherwise stated.

These conditions have been applied to satisfy the relevant requirements of the *Environmental Planning & Assessment Act 1979, Environmental Planning & Assessment Regulation 2000*, Council's development consent and to maintain reasonable levels of public health, safety and amenity.

Occupation Certificate Requirements

32. An Occupation Certificate must be obtained from the Principal Certifying Authority prior to any occupation of the building work encompassed in this development consent (including alterations and additions to existing buildings), in accordance with the relevant provisions of the *Environmental Planning & Assessment Act 1979*.

BASIX Requirements & Certification

33. In accordance with Clause 154B of the *Environmental Planning & Assessment Regulation 2000*, a Certifying Authority must not issue an Occupation Certificate for this development, unless it is satisfied that any relevant BASIX commitments and requirements have been satisfied.

Relevant documentary evidence of compliance with the BASIX commitments is to be forwarded to the *Principal Certifying Authority* and Council upon issuing an Occupation Certificate.

Council's Infrastructure, Vehicular Crossings, street verge

34. The applicant must meet the full cost for Council or a Council approved contractor to repair/replace any damaged sections of Council's footpath, kerb & gutter, nature strip etc which are due to building works being carried out at the above site. This includes the removal of cement slurry from Council's footpath and roadway.
35. All external civil work to be carried out on Council property (including the installation and repair of roads, footpaths, vehicular crossings, kerb and guttering and drainage works), must be carried out in accordance with Council's "Crossings and Entrances – Contributions Policy" and "Residents' Requests for Special Verge Crossings Policy" and the following requirements:
 - a) Details of the proposed civil works to be carried out on Council land must be submitted to Council in a Civil Works Application Form. Council will respond, typically within 4 weeks, with a letter of approval outlining conditions for working on Council land, associated fees and workmanship bonds. Council will also provide details of the approved works including specifications and construction details.
 - b) Works on Council land, must not commence until the written letter of approval has been obtained from Council and heavy construction works within the property are complete. The work must be carried out in accordance with the conditions of development consent, Council's conditions for working on Council land, design details and payment of the fees and bonds outlined in the letter of approval.

- c) The civil works must be completed in accordance with the above, prior to the issuing of an occupation certificate for the development, or as otherwise approved by Council in writing.

Stormwater Drainage

36. The applicant shall submit to the Principal Certifying Authority (PCA) and Council, certification from a suitably qualified and experienced Hydraulic Engineer confirming that the design and construction of the stormwater drainage system complies with Australian Standard 3500.3:2003 (Plumbing & Drainage-Stormwater Drainage) and the conditions of this development approval. The certification must be provided following inspection/s of the site stormwater drainage system by the certifying engineers and shall be provided to the satisfaction of the PCA.

Landscaping

37. Prior to issuing any Final Occupation Certificate, certification from a qualified professional in the landscape/horticultural industry must be submitted to, and be approved by, the PCA, confirming the date that the completed landscaping was inspected, and that it has been installed substantially in accordance with the Landscape Plans by Robert Finnie Design, dwg's DA01-03, rev A, dated 22/08/18.
38. Suitable strategies shall be implemented to ensure that the landscaping is maintained in a healthy and vigorous state until maturity, for the life of the development.
39. That part of the nature-strip upon Council's footway which is damaged during the course of the works shall be re-graded and re-turfed with Kikuyu Turf rolls, including turf underlay, wholly at the applicant's cost, to Council's satisfaction, prior to the issue of any Occupation Certificate

GENERAL ADVISORY NOTES

The following information is provided for your assistance to ensure compliance with the *Environmental Planning & Assessment Act 1979*, *Environmental Planning & Assessment Regulation 2000*, or other relevant legislation and requirements. This information does not form part of the conditions of development consent pursuant to Section 4.17 of the Act.

- A1 The requirements and provisions of the *Environmental Planning & Assessment Act 1979* and *Environmental Planning & Assessment Regulation 2000*, must be fully complied with at all times.

Failure to comply with these requirements is an offence, which renders the responsible person liable to a maximum penalty of \$1.1 million. Alternatively, Council may issue a penalty infringement notice (for up to \$3,000) for each offence. Council may also issue notices and orders to demolish unauthorised or non-complying building work, or to comply with the requirements of Council's development consent.

- A2 In accordance with the requirements of the *Environmental Planning & Assessment Act 1979*, building works, including associated demolition and excavation works (as applicable) must not be commenced until:

- A *Construction Certificate* has been obtained from an Accredited Certifier or Council,
- An Accredited Certifier or Council has been appointed as the *Principal*

- *Certifying Authority* for the development,
Council and the Principal *Certifying Authority* have been given at least 2 days notice (in writing) prior to commencing any works.

A3 Council can issue your *Construction Certificate* and be your *Principal Certifying Authority* for the development, to undertake inspections and ensure compliance with the development consent and relevant building regulations. For further details contact Council on 9093 6944.

A4 This determination does not include an assessment of the proposed works under the Building Code of Australia (BCA) and other relevant Standards. All new building work (including alterations and additions) must comply with the BCA and relevant Standards and you are advised to liaise with your architect, engineer and building consultant prior to lodgement of your construction certificate.

A5 Any proposed amendments to the design and construction of the building may require a new development application or a section 4.55 amendment to the existing consent to be obtained from Council, before carrying out such works

A6 A Local Approval application must be submitted to and be approved by Council prior to commencing any of the following activities on a footpath, road, nature strip or in any public place:-

- Install or erect any site fencing, hoardings or site structures
- Operate a crane or hoist goods or materials over a footpath or road
- Placement of a waste skip or any other container or article.

For further information please contact Council on 9093 6971.

A7 Specific details of the location of the building/s should be provided in the Construction Certificate to demonstrate that the proposed building work will not encroach onto the adjoining properties, Council's road reserve or any public place.

A8 This consent does not authorise any trespass or encroachment upon any adjoining or supported land or building whether private or public. Where any underpinning, shoring, soil anchoring (temporary or permanent) or the like is proposed to be carried out upon any adjoining or supported land, the land owner or principal contractor must obtain:

- the consent of the owners of such adjoining or supported land to trespass or encroach, or
- an access order under the *Access to Neighbouring Land Act 2000*, or
- an easement under section 88K of the *Conveyancing Act 1919*, or
- an easement under section 40 of the *Land & Environment Court Act 1979*, as appropriate.

Section 177 of the *Conveyancing Act 1919* creates a statutory duty of care in relation to support of land. Accordingly, a person has a duty of care not to do anything on or in relation to land being developed (the supporting land) that removes the support provided by the supporting land to any other adjoining land (the supported land).

A9 The finished ground levels external to the building must be consistent with the development consent and are not to be raised, other than for the provision of approved paving or the like on the ground

- A10 Prior to commencing any works, the owner/builder should contact *Dial Before You Dig* on 1100 or www.dialbeforeyoudig.com.au and relevant Service Authorities, for information on potential underground pipes and cables within the vicinity of the development site.
- A11 An application must be submitted to an approved by Council prior to the installation and operation of any proposed greywater or wastewater treatment systems, in accordance with the *Local Government Act 1993*.
- Greywater/Wastewater treatment systems must comply with the relevant requirements and guidelines produced by NSW Health, NSW Office of Environment and Heritage and other relevant regulatory requirements.
- A12 Underground assets (eg pipes, cables etc) may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial before you dig at www.1100.com.au or telephone on 1100 before excavating or erecting structures (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial before you dig service in advance of any construction or planning activities.
- A13 The applicant is to advise Council in writing and/or photographs of any signs of existing damage to the Council roadway, footway, or verge prior to the commencement of any building/demolition works.
- A14 Further information and details on Council's requirements for trees on development sites can be obtained from the recently adopted Tree Technical Manual, which can be downloaded from Council's website at the following link, <http://www.randwick.nsw.gov.au> - Looking after our environment – Trees – Tree Management Technical Manual; which aims to achieve consistency of approach and compliance with appropriate standards and best practice guidelines.